

# CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

FEBRUARY 1960



VOL. LV. NO. 2

FIFTY-FIFTH YEAR OF PUBLICATION

PRICE 2s.

ANNUAL SUBSCRIPTION 24s. POST FREE. £3.00 in Canada and U.S.A.

## LEADING CONTENTS

	PAGE
A Code for Prestressed Concrete in Buildings . . . . .	69
Stresses Permissible in Prestressed Concrete By P. W. Abeles, D.Sc., M.I.Struct.E. . . . .	73
Concreting Plant at a Nuclear Power Station in Scotland . . . . .	83
Nomograms for the Design of Beams and Slabs by the Load-factor Method.—I. By J. C. Steedman . . . . .	91
A Chapel at an Oxford College . . . . .	101
Mesh Reinforcement for Doubly-curved Slabs . . . . .	103
Deep Cylindrical Foundation Piers . . . . .	105

No. 627

ISSUED MONTHLY

Registered for  
Canadian Magazine Post

## BOOKS ON CONCRETE

For Catalogue of "Concrete Series" books on concrete and allied subjects, send a postcard to:

CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., LONDON, S.W.1.

## INDEX OF ADVERTISERS

	Page		Page
A.B. Mould & Construction Co. Ltd.	xxvii	LAPORTE ALUMINOUS CEMENT Co. Ltd.	liii
ARMSTRONG & Co. (Engineers) Ltd.	xxx	LAW & SON (STAINERS) LTD.	vi
A.C.E. Machinery Ltd.	—	LEARY'S FISHBOARDS LTD.	—
ALLAN, E. F., & Co. Ltd.	lvii	LEIDA OIL & Grease Co. Ltd.	xxx
		LEISCRETE LTD.	xlvi
		LESLINGTON, GEORGE, & Co. LTD.	1
		LIND, PETER, & Co. LTD.	ix
BERRY'S ENGINEERING Co.	xxxi		
BOYER, WM., & SONS LTD.	xi	McCALL & Co. (SHEFFIELD) LTD.	xii
BRATHWAITE FOUNDATIONS & CONSTRUCTION LTD.	xiii	McCALLS MACALLOY LTD.	xxv
B.R.C. ENGINEERING Co. LTD.	xxviii	McKINNEY FOUNDATIONS LTD.	xviii
BRITISH STEEL PILING Co. LTD.	—	MAY & BUTCHER LTD.	viii
BYRD, A. A., & Co. LTD.	ix	MICANTIS & INSULATIONS Co. LTD.	—
		MILBARK FLOORS LTD.	xlvi
CAPLEN ENGINEERING Co. LTD.	ix	MILLARS' MACHINERY Co. LTD.	—
CEMENT MARKETING Co. LTD.	xviii	MILLS SCAFFOLD Co. LTD.	xxvii
CHEMIST & STEEL LTD.	vi	MONK, A., & Co. LTD.	—
CHAPMAN, H. W. LTD.	—	MORAN, WHITLEY, & Co. LTD.	—
CHEMICAL BUILDING PRODUCTS LTD.	xiv	MULCAHER, WM., & Co. (Contractors) LTD.	iv
CHERRHAM, ALAN J., LTD.	xxviii		
COLCRETE LTD.	ii	P.B.C. EQUIPMENT Co. LTD.	x, xi
COLVILLE LTD.	xv	PASHLEY & TRACKETT LTD.	—
COMPACTORS ENGINEERING LTD.	xvi	PORTABLE LTD.	lviii
CONCRETE PILING LTD.	xvii	PREFABRICATED SALES LTD.	—
CONCRETE PROOFING Co. LTD.	xxviii	PRIEST, B., & SONS LTD.	xiii
CONCRETE PUBLICATIONS LTD.	xxvii, vi	PYFORD LTD.	xlvi
CONCRETE PUMP Co. LTD.	xxvii		
CONCRETE SERVICES LTD.	vi		
CONVEYERS & Co. LTD.	xlvi		
CORSELY EQUIPMENT Co. LTD.	—		
D.A. MODELS LTD.	iii	RAHALAN STEEL MOUNDS LTD.	xi
DAVIDSON'S PAPER SALES LTD.	—	RAWLINGS Co. LTD.	xxviii
DEKINS, STUART B., LTD.	xlv	ROVER CAR Co. LTD.	—
DERRAN LONG & Co. LTD.	—	RYLANDS BROTHERS LTD.	—
ENGINEERING DESIGN & CONSTRUCTION LTD.	xv	SAMUEL & SON LTD.	xxiii
EVANS LTD.	xxii, xxiii	SEALCONCRETE PRODUCTS LTD.	xxvii
EXPANITE LTD.	—	SEMON-CARVER LTD.	—
		SHIPLEY CONCRETE PILES LTD.	lv
FEB (Great Britain) LTD.	iii	STALING LTD.	ix
FLEXIBLE DRIVE & TOOL Co. LTD.	ix	STEEL PRECAST CONCRETE LTD.	—
FORD MOTOR Co. LTD.	xvii	STIC B PAINT SALES LTD.	—
FRANKILE LTD.	xix	STONE COURT BALLAST Co. LTD.	xlv
		STONES, WM. T., & Co. LTD.	xxvi
		STREAMING DEVELOPMENTS LTD.	v
		STUART'S GRADING Co. LTD.	—
G.K.M. REINFORCEMENTS LTD.	lii	TECHNICAL PAINT SERVICES	xxix
GLASSON, M. J. (Contractors) LTD.	xvii	TERRELLS LTD.	xii
GUNITE CONSTRUCTION Co. LTD.	ix	TENDON BAR Co. LTD.	xxvii
		THAMES PLYWOOD MANUFACTURERS LTD.	—
		THOMAS & PRICE (THAMES) LTD.	—
HILL, RICHARD, LTD.	xxvii	TIMBER GRAVELS LTD.	xxvii
HILTON GRAVEL LTD.	—	TUNNELL PORTLAND CEMENT Co. LTD.	—
HOLLAND & HANSEN AND COMPANY (Gt. Britain) LTD.	—		
HOLT & Co. LTD.	—		
HUNTLEY & SPARKS LTD.	xxvii		
IMPERIAL CHEMICAL INDUSTRIES LTD.	—		
JOHNSON, RICHARD, & NEWBREW LTD.	xlv	WALKER WRIGHT & Co. LTD.	—
JOHN, T. C., & Co. LTD.	lv	WALSHACK TRADING Co. LTD.	xlvi
		WESTWOOD, JONES, & Co. LTD.	iii
		WHITHEAD IRON & STEEL Co. LTD.	—
		WHITLEY MORAN & Co. LTD.	—
MARKEE-GREENWOOD & Co. LTD.	—		
KING, J. A., & Co. LTD.	xiii	YORKSHIRE MANUFACTURING CONTRACTING Co. LTD.	—

# **1½ MILLION CUBIC YARDS OF CONCRETE HAVE BEEN AIR-ENTRAINED WITH FEBCRETE A.E.A.**

**ON BRITISH GOVERNMENT CONTRACTS  
DURING THE PAST TWO YEARS**

FEBCRETE Air-Entraining Agent without adding to cost improves the flowability and workability of concrete, allows the water-cement ratio to be reduced and increases resistance to the passage of water and to repeated cycles of freezing and thawing.

It ensures that full compaction and maximum compressive strength are obtained without excessive vibration, reduces segregation of the aggregates and prevents bleeding. Write for brochure.

**FEB** (GREAT BRITAIN) LTD

LONDON: 102 Kensington High Street, W.8.


Telephone: WEStern 0444

MANCHESTER: Albany Works, Albany Road, Chorlton-cum-Hardy.

Telephone: CHOrlton 1063

# WOOD MOULD

for roof-light surrounds for



The mould illustrated above is 10 ft. by 10 ft., and is one of many designed and supplied by us for this contract.

We are specialist mould makers to the concrete industry, and can supply wooden moulds for all types and sizes of precast concrete. Accuracy is guaranteed in every detail and 25-years' experience is always at your service. Many new methods introduced by **LAWS & SONS** have been adopted by our customers for use in their own shops.

MESSRS.  
**WATES LTD**

In the  
construction of the

**U.S.A.  
EMBASSY  
LONDON**

## LAWS

**& SONS (STAINES) LTD.**

(CONTRACTORS TO  
H.M. GOVERNMENT)

Langley Road Works, Staines,  
Middlesex  
Telephone: Staines 53700

# GUNITE SPECIALISTS

## WM. MULCASTER

**& CO. (CONTRACTORS) LTD.**

We invite inquiries for Gunite Linings and Renderings  
for new or old structures of every kind in any part  
of the country.

**HASLINGTON**

**CREWE**

Telephone: Crewe 2265-6.



***If you want to pre-tension  
economically and efficiently —  
consult the specialists in this field***


**WIRE AND STRAND GRIPS  
PLAIN AND SPRING-LOADED**

**HYDRAULIC RAMS  
25 TO 200 TONS CAPACITY  
3" TO 36" EXTENSION**

**HYDRAULIC HAND AND  
POWER PUMPS TO SUIT  
ALL RAM SIZES**

**UNIVERSAL PULL-CARRIAGES  
FOR MULTIPLE STRESSING  
IN UNITS OF 50, 100  
AND 150 TONS**

**STRESSING BED DESIGNS  
SUPPLIED FREE WITH ALL  
EQUIPMENT ORDERS  
COMPLETE PLANT LAYOUTS  
UNDERTAKEN BY ARRANGEMENT**




SEND FOR BOOKLET AND PRICE LIST TO

**STRESSING DEVELOPMENTS LTD.**

95 KINGSTON HILL, KINGSTON-UPON-THAMES

TELEPHONE: KINGSTON 2372



# POWER BAR CUTTERS


The BRRL.5A model, illustrated above, will meet all requirements for high speed, economy, and simplicity of operation. This high-speed shearing machine will cut mild steel rods up to 2 in. diameter. It is of robust construction yet portable in view of its compact arrangement, and is powered by electric motor and self-tensioning Vee-belt drive. The moving blade is in continuous action and makes 28 cuts per minute; 2-in. diameter bars require one cut only. The static blade is housed in a specially designed seating which spreads the shearing thrust over a wide area, thus reducing wear and considerably lengthening the life of the machine. Let us send you full details.

**CEMENT & STEEL, LTD., SECOND AVENUE, CHATHAM, KENT**

Telephone: Chatham 45580. Telegrams: Cambulgi, Chatham.



**MODERNISATION OF MOTIVE POWER DEPOT, YORK**



Arched ribs in Concrete Spanning 55 ft. on to framed steel beams 204 feet in length.

Completed section in foreground is of pre-stressed concrete beam construction bearing on in-situ columns and is glazed throughout.


Photographs by kind permission of British Railways.

*For the design, manufacture and erection of concrete structures*

**consult**

**Concrete Services Ltd**

ODDE ACRES · BOROUGHERIDGE ROAD · YORK Tel. 76475



# POWER BAR CUTTERS


The BRRL.5A model, illustrated above, will meet all requirements for high speed, economy, and simplicity of operation. This high-speed shearing machine will cut mild steel rods up to 2 in. diameter. It is of robust construction yet portable in view of its compact arrangement, and is powered by electric motor and self-tensioning Vee-belt drive. The moving blade is in continuous action and makes 28 cuts per minute; 2-in. diameter bars require one cut only. The static blade is housed in a specially designed seating which spreads the shearing thrust over a wide area, thus reducing wear and considerably lengthening the life of the machine. Let us send you full details.

**CEMENT & STEEL, LTD., SECOND AVENUE, CHATHAM, KENT**

Telephone: Chatham 45580. Telegrams: Cambelgi, Chatham.



**MODERNISATION OF MOTIVE POWER DEPOT, YORK**



Arched ribs in Concrete Spanning 55 ft. on to framed steel beams 204 feet in length.

Completed section in foreground is of pre-stressed concrete beam construction bearing on in-situ columns and is glazed throughout.


Photographs by kind permission of British Railways.

*For the design, manufacture and erection of concrete structures*

**consult**

**Concrete Services Ltd**

90 DE ACRES • BOURGOMBRIDGE ROAD • YORK • TEL 70475



### **35-TONS PRECAST BRIDGE SECTION**

We illustrate one of the 35-ton sections produced by Anglian Building Products Ltd., of Atlas Works, Lenwade, Norwich, and 67 Jermy Street, London, W.1, for British Railways L. M. Region. Main Contractors: Leonard Fairclough Ltd.

# **WOODEN MOULD**

*was produced by*

# **MAY & BUTCHER LTD**

**SPECIALISTS IN TIMBER SHUTTERS AND MOULDS FOR CONCRETE**


More and more Contractors and Precast Concrete Makers in all parts of the country are taking advantage of the first-class service we offer in the supply of timber shutters and moulds to any design and size. This service has proved over and over again that by ordering your shutters and moulds from us you effect every possible saving in time, labour and money. However intricate the shutter or mould, you are assured of accuracy in every detail and a product with long trouble-free life. Shutters and moulds can be supplied with a plastic lining if desired. Full details of this class of work carried out by us are available on request.

**HEYBRIDGE BASIN, MALDON, ESSEX.**

**TELEPHONE: MALDON 698/9**



**TRANSIT WAREHOUSE  
FOR  
MERSEY DOCKS AND  
HARBOUR BOARD**



Engineers  
The British

**PETER LIND & CO LTD**

ROMNEY HOUSE, TUFTON STREET, LONDON, S.W.1

TELEPHONE ABBEY 7341

# PSC for all

## FREYSSINET SYSTEM



The illustration on the left shows the Freyssinet System of cone anchorage, with "Hydrarigid" sheathing. It is normally cast in the end of the member to be prestressed, and is usually recessed to permit a protective mortar covering to be applied after grouting. Anchorage cones are provided for 8/200, 10/200, 12/200, and 12/276 cables.



One of the most recent developments in the Freyssinet system of prestressing has been the introduction of power stressing. An electric or I.C. operated motor driving an hydraulic pump is trailer mounted and the hydraulic circuit has been simplified to only two controls which require the operator's attention. These are mounted on the trailer assembly and the jack is thus completely remote-controlled. The advent of power stressing has increased the rate of tensioning by three or four times that of hand pumping.


## P.S.C. MONOWIRE SYSTEM



... P.S.C. ANCHORAGE The 8/276 P.S.C. "MonoWire" Anchorage illustrated here shows a "Hydrarigid" welded seam-jointed metal sheath which screws into the anchorage. A new type of high-impact plastic cable spacer is also available. These anchorages can be supplied for cables of one to twelve wires.

## P.S.C. MONOWIRE POST-TENSIONING ...

This illustration shows the P.S.C. lightweight single-wire jack stressing one of twelve wires on a 12/276 "MonoWire" anchorage. The jack is available with 4' or 6' extensions, and has a spring return.



# prestressing equipment



## ... P.S.C. GROUTING EQUIPMENT

We have made considerable investigations into the grouting of prestressed cable ducts, particularly with regard to the composition of the grout, its mixing and injection. This experience has enabled us to produce trouble-free grout injection pumps, both hand and power operated, designed specifically for cable-duct grouting. The illustration shows the use of hand diaphragm-operated direct-displacement grouting equipment.

## P.S.C. MONOWIRE PRE-TENSIONING ...

The P.S.C. "MonoWire" pre-tensioning jack illustrated here is available with extensions from 9' to 24'. The hand-operated equipment is extended hydraulically and returned pneumatically. The power-operated pump (electric or I.C.) is recommended where a large number of long extensions is anticipated.




## HYDRADUCT SHEATHING FOR PRESTRESSED CONCRETE

This range of sheathing includes "Hydrarigid" and "Hydraflex". It is highly efficient and easy to use, and is strong enough to take the weight of men without damage, yet flexible enough for all normal prestressing requirements. Supplied in standard lengths in diameters from 2" to 4".

## ... BRIDGE BEARING PADS


The Freyssli Bearing Pad,

illustrated here, has proved its economy and efficiency on over 400 bridge contracts. Each pad is designed specifically for individual requirements from information obtained from a technical questionnaire, on which we ask certain design considerations. Full details are available on request.



## FREYSSI FLAT JACKS ...

Freyssi Flat Jacks are hydraulic jacks of unusual and unconventional design, which permit enormous forces to be exerted or regulated where the movement required is small. They have applications in underpinning, levelling and thrust control in engineering structures.



# PSC



EQUIPMENT LTD


HEAD OFFICE AND WORKS: ARUNDEL ROAD, INDUSTRIAL TRADING ESTATE, UXBRIDGE, MIDD<sup>X</sup>

Telephone: Uxbridge 5242

PIONEERS OF PRESTRESSED CONCRETE IN GREAT BRITAIN

# GLASS FIBRE SHUTTERING

for all in-situ concrete work



Glass Fibre is unequalled as a material for simple and intricate shuttering for all forms of concrete construction. The illustration on the left shows glass fibre shuttering supplied by us for columns with splayed heads for new premises constructed by Gravesend Wholesale Co-operative Society. Architect: Mr. W. J. Reed, F.R.I.B.A.

**NO STICKING • NO CLEANING**  
**STRONG AS STEEL • FIRM AS A ROCK**

**FOR HIRE** Glass Fibre Moulds for Flooring

**Consult**

**D. A. MODELS • LTD**

106 WOODSTOCK ROAD, LONDON. W.4.

TELEPHONE: CHISWICK 2011



**Building and Civil Engineering**

**Contractors**

with wide experience

of power station

construction

railway development

road development

and coast protection schemes

prestressed concrete

bridge building

multi-storey flats

Contractors to the

CEGB/UKAEA/BR/NCB/LCC and other

national and local authorities, and to leading

architects and consulting engineers



LONDON

MANCHESTER

**GLEESON**


SHEFFIELD

**M. J. GLEESON (CONTRACTORS) LTD.**

Haredon House, London Road,

North Cheam, Surrey

Telephone: Fairlands 4321 (8 lines).



### OUTSTANDING BUILDING ...

#### *Outstanding products . . .*

**CHEMICAL  
BUILDING  
PRODUCTS  
LIMITED**  
Warple Works  
Cleveland Road  
Hemel Hempstead  
Herts.

**PROLAPIN** Liquid Cement Waterproof  
**LITHURIN** Concrete Floor Hardener  
**QUICKSocreTE** P.Q. & D. Rapid Hardeners and  
Setters  
**WETEXI 'S'** Colourless Silicone Waterproof  
**CONPLAST** Concrete Plasticiser  
**CONPLAST 'W'** Anti-freeze and Plasticiser  
**CEBEX 112** Mortar Improver  
**CEBEX 113** Expanding Grouting Material  
**CEBEX 124** Multi-purpose Slurry Liquid  
**ROAD CONPLAST** Air Entrainer and Plasticiser  
**CONBEX** Plasticised Expanding Grouting Material


### CHEMICAL BUILDING PRODUCTS LTD

Telephone: Boxmoor  
4900 (5 lines)  
Telegrams: Frolithu  
Hemel Hempstead

We shall be pleased  
to supply full des-  
criptive literature.

**LIFTOYL** Floor Cleaner and Degreaser  
**ORKIT & TEKTAM** Bituminous Coatings and  
Compounds  
**CONCURE** Concrete Curing Agent  
**NITOLUX & ROBRITE** Paints





A FIRST-CLASS SERVICE FOR ALL TYPES OF

## **REINFORCEMENT**

DESIGN SUPPLY BENDING AND FIXING OF  
MILD STEEL, COLD WORKED BARS AND  
HIGH TENSILE FABRIC

WE ARE THE SOLE MANUFACTURERS OF

# **COROBAR**

(TRADE MARK)

THE COLD WORKED BAR  
FOR

## **CONCRETE REINFORCEMENT**

OFFICES :

ARDSHIEL HOUSE  
EMPIRE WAY  
WEMBLEY, MDDX.




WORKS :

RIGBY LANE  
DAWLEY ROAD  
HAYES, MDDX.

**THE ENGINEERING DESIGN & CONSTRUCTION  
COMPANY LIMITED**

TELEPHONE: WEMBLEY 9474    TELEGRAMS: EDCON WEMBLEY



**MODEL  
A.15**

**1½ IN. DIA.  
ONLY**



## **THE NEW AIR VIBRATOR**

**specially designed to cater for  
the compacting requirements of  
low-slump concrete and all  
other designs of concrete mixes**

The Model A.15 Air Vibrator, with its high frequency of 12,000 r.p.m. combined with a large amplitude, is a ready and effective answer to the problem of using a vibrator with a small diameter head for compacting a low-slump concrete. It enables the driest of concrete mixes to be thoroughly compacted with the minimum of delay.

The diameter of its head is 1½ in. only. Its weight is 5 lb., and its air consumption 20 cu. ft.


**TEST IT ON YOUR CONTRACT  
WITHOUT OBLIGATION**

The A.15 model is available at short notice for sale or hire. Let us send you full details.

# **COMPACTORS ENGINEERING LTD.**

LOCKFIELD AVENUE, BRIMSDOWN, ENFIELD, MIDDX. Telephone: Howard 4063-5

Underreamed boring  
**DOWN TO 110 FEET**




with the  
**Mc KINNEY**  
Mobile Rig



If you would like further  
details, please write to:

**McKINNEY FOUNDATIONS LIMITED**

Manor Way, Boreham Wood, Hertfordshire. Telephone: Elstree 2854



## Take no chances

*When there is risk of  
danger to concrete by contamination  
from soluble sulphates  
in soil or water*

# USE SULFACRETE

---


The only Sulphate-resisting Portland Cement

which has given proved protection in practice and  
in exposure tests over the last 10 years.




Dense concrete made with Sulfacrete  
is proof against attack by concentrations  
of sulphates in terms of sulphur  
trioxide up to 0.5 per cent by  
weight in ground water and 2.0 per  
cent by weight in soil or clay.

Write for full details to: **THE CEMENT MARKETING CO. LTD.** Portland House, Tothill St., London, S.W.1, or **G. & T. EARLE LIMITED**, Hull or **THE SOUTH WALES PORTLAND CEMENT & LIME CO. LTD.**, Penarth, Glam.



**FRANKIPILE**

**Large  
Diameter  
Bored  
Piles**



For compacting mortar cubes  
for compression tests to

B.S. 12/1958, 146, 1370, 915

Automatic Time Control

# "CAPCO"

## H.F. VIBRATOR

"CAPCO" CONCRETE TESTING APPARATUS also includes:  
Cube Moulds; Slump Cones; Tensile, Vicat and Cylindrical  
Moulds; Compacting Factor Apparatus—Standard and Auto-  
matic; Sieve Vibrators and Sieves; etc.

### CAPLIN ENGINEERING CO. LTD

ALPAX WORKS, ST. LEONARDS ROAD, WILLESDEN JUNCTION, LONDON, N.W.10

\*Phone: ELGAR 7191. Grams: CAPLINKO, London, N.W.10. Cables: CAPLINKO, LONDON



For Greater Strength, Firmer Bonding  
and Better Surfacing of Concrete—

# "BAXTUL"

Regd. Trade Mark

British Made

Extra-High Frequency

### INTERNAL CONCRETE VIBRATORS

● The model illustrated here operates at 9,000 to 15,000 Vibrations per minute from low flexible shaft speeds of 4,500 to 7,500 R.P.M.

● Petrol or Electric Drive.

● Robustly built throughout and backed by genuine service.

● Fitted centrifugal clutch, long-life flexible drive and Vibrator.

This unique machine, with quick-change additional tools, can also be used for: SURFACING, WET-RUBBING CONCRETE, GRINDING, DISC SANDING, AND DRILLING (up to 1½" in Concrete, 1" in Steel, and 2" in Wood).

Model VP 338-A (Swivel Base or Serraw Mounting)

Prompt Delivery. Highly Competitive Prices. Genuine Service. Re-Sale Terms Available.

\* We operate a 48-hour Shaft Repair Service for all makes. Write to-day for 8-page fully descriptive Catalogue. Agents throughout the world.

30 years' experience in the design and manufacture of flex-shaft tools.

### THE FLEXIBLE DRIVE & TOOL CO., LTD.

EDENBRIDGE, KENT. Telephone: 3385-4

LONDON OFFICE: 17 QUEENSBERRY WAY, S.W.7. Telephone: KENington 3583



**Top quality & service**

**Site investigations**

**Bored piling & Foundations**

**Materials & Structural testing**



—Terresearch service has proved its worth—

Terresearch specialists have a wide, practical experience in all branches of building and civil engineering, and full resources for carrying out investigations and research and sound speedy construction.

**WE HAVE SUCCESSFULLY CARRIED OUT  
SUCH WORK FOR:**

ATOMIC AND THERMAL POWER STATIONS · AIRFIELD WORKS  
RAILWAY WORKS · BRIDGES · ROAD WORKS  
MARINE AND HYDRAULIC WORKS · MULTI-STOREY OFFICES  
AND APARTMENTS · FACTORIES, etc.


OUR BROCHURE IS YOURS BY REQUEST

***T*erresearch LIMITED**

BUILDING AND CIVIL ENGINEERING LABORATORY  
PILING AND FOUNDATION ENGINEERS & CONTRACTORS

RUISLIP ROAD · NORTHOLT GREENFORD MIDDLESEX Telephone: WAXlow 6341-3

## Why more and more contractors



**IN BRITAIN** Darex AEA was used throughout in the concrete construction of the Glendevon Dam



**IN BRITAIN** Darex AEA was incorporated in the bulk concrete of the North of Scotland Hydro Electric Board's Aitt-na-Lairige Dam


\* The first and foremost Air Entraining Agent

\* Used in the U.S.A. for more than 27 years on major projects

\* In use throughout the world

Darex AEA is the original air entraining agent that has proved itself throughout the world for Dam Construction, Structural Concrete, Roads and Aerodromes, Bridges, Maritime Works and Concrete products. America, Belgium, Canada, Norway, Portugal, Sweden, Switzerland and many other countries acclaim Darex AEA as the first and foremost air entraining agent.

TECHNICAL SERVICE may be obtained from the sole U.K. distributors



OF STAFFORD

Are YOU using the EVODE PERSONAL SERVICE TO DESIGNERS? Write or phone for details.

**EVODE LTD., (BUILDING CHEMICALS DIVISION) STAFFORD Tel: 2241 (5 lines)**

# ask for **Darex AEA** as the fifth ingredient for concrete

DAREX AEA, a ready-to-use, dark brown liquid, is an aqueous solution of triethanolamine salts of a sulfonated hydrocarbon. For smoother flow and finer finishing, it lubricates the concrete mix with millions of tiny air bubbles. It also contains a catalyst which promotes more rapid and complete hydration of portland cement. Not a resin or by-product, DAREX AEA is a chemical formulation manufactured to insure predictable performance. It is harmless and neutral and requires no pre-mixing with corrosive chemicals or water.

DAREX AEA is ideally suitable for ready mixed concrete, structural concrete, mass concrete construction, concrete road construction, repairs and patching and concrete products.

- Air bubbles guard against frost damage and cracking even with repeated freezing and thawing.

- Makes concrete resistant to saline solutions, de-icing salts, sulphate and sea waters.

- Less mixing water can be used with no loss in slump.

- Improves placeability.

- Air bubbles lubricate and plasticize the mix.


- Minimizes bleeding, green shrinkage and segregation.

- Catalyst promotes faster and more thorough hydration, thus bringing out more of inherent strength of portland cement; assures greater strength in both lean and rich mixes than non-catalysed air entraining agents.

- Will not entrain excessive air.

- Particularly effective with slag, lightweight or manufactured aggregates that tend to produce harsh concrete.

- Permits use of natural sand deficient in fines.



## Reduce water with **WRDA**

WRDA, an aqueous solution of highly purified metallic salts of lignin sulfonic acid, is a ready-to-use, non-setting, dark brown, mobile liquid. It acts as a dispersing and plasticizing agent—makes possible easily placeable mixes with up to 20% less water content and a corresponding increase in strength and durability. It contains a catalyst which counteracts the normal hydration-retarding effect of dispersing admixtures; and a preservative. It is compatible with all known air entraining agents. WRDA does not require agitation, it comes ready-to-use.

- WRDA reduces natural interparticle attraction of cement grains and makes the mix more workable and placeable with less water.

- Gives low slumps without loss of placeability.

- Makes concrete flow cleanly around reinforcing steel and respond quickly to vibration, spading and compacting.

- Improves water retention and internal cohesiveness of the plastic mix.

- Cuts green and drying shrinkage.

- Reduces bleeding, honeycombing, water gain voids under aggregate and other segregation.

- Allows concrete floors to be finished sooner.

- Increases compressive strength up to 25%; also increases flexural and tensile strengths.

- The action on cement is physical. It does not change the chemical properties.

- Improves appearance of concrete by sharply reducing spalling, leaching and sand streaking.

AIR METERS AND DISPENSERS ARE READILY AVAILABLE

London Office: 82 VICTORIA STREET, S.W.1. Tel: ABBey 4622 (5 lines)

W-4-112

# STONE COURT AGGREGATES



*General View of Plant at Rickmansworth.*

## ONE OF OUR MODERN CONCRETE AGGREGATES PLANTS

First-Class Washed graded concrete aggregates, and shingles for road dressing, coupled with efficient delivery, are at the service of contractors and Municipal Authorities in London, Berks, Bucks, Herts, and Middlesex Areas.

Our products include Washed Sharp Sand, all sizes of shingles, from 3/16" up to 2", either crushed or natural.

Special Specifications made to order.



**STONE COURT BALLAST CO. LTD.**  
PORTLAND HOUSE, TOTHILL ST., WESTMINSTER, S.W.1

Telephone: Abbey 3456.





## STEEL GIVES STRENGTH

Colvilles have built up a reputation as suppliers of all types of Structural Steel - Light and Heavy Sections, Joists and Plates - to all specifications. Colvilles can supply a range of High Strength Steels under our DUCOL series with a minimum yield strength of 23 tons per square inch and upwards.

These special steels are in regular production and can be supplied in accordance with our rolling programme.



# COLVILLES

FITNESS FOR PURPOSE STEELS

COLVILLES LIMITED 193 West George St., Glasgow C.2.

# STORERS

WM. T. STORER & Co. LTD.

TIMBER IMPORTERS AND MERCHANTS

*Established 1913*



*Sawing and Planing Mills:*

RIVER ROAD, BARKING, ESSEX

Telephone: RIPPleway 0301 (10 lines)

FOR  
SOFTWOOD



# Canute couldn't stop it ...

## Sealocrete P.V.C. Waterbar can !

Inserted between each lift, whilst the concrete is being placed, Sealocrete P.V.C. Waterbar ensures there is no seepage of water through floor to wall and construction joints. Sealocrete P.V.C. Waterbar is made of a special grade of unfilled Polyvinyl Chloride, is chemically inert, non-corrosive and resistant to ageing.

Being flexible, it is specially recommended for joints where limited movement is expected. Cross and Tee Sections can also be supplied pre-fabricated. Possessing all the properties of P.V.C. Waterbar, plus greater rigidity, SEALOCRETE Corrugated Bitumised Waterbar (Patented) combines maximum handling facility with lower cost—and may be preferred in specific applications.

*Write for descriptive leaflets giving full information.*



**SEALOCRETE PRODUCTS LIMITED**



ATLANTIC WORKS · HYTHE ROAD · LONDON · N W 10

TEL Ladbroke 0015 FBE

TELEGRAMS & CABLES: SEALOCRETE, WESPHONE, LONDON



### SIZES AND SECTIONS



VERTICAL CROSS



VERTICAL TEE



FLAT TEE



FLAT CROSS

# CUT YOUR CONCRETE COSTS

*with the*

# A.B. MOULD

## MIXER-DRIVE SHOVEL


**ALL-BRITISH DESIGN AND MANUFACTURE**

*(Patent applied for)*

### **At last !**

The perfect combination of a winch unit attached to and driven by the mixer, but operated from the press-button-controlled shovel.

**THE BUILT-IN JIB ELIMINATES  
SITE INSTALLATION COSTS.**



**LOW CAPITAL OUTLAY RECOVERED IN TEN WEEKS**

**NO RUNNING COSTS**

**FITTED TO MOST MIXERS**

*Ask for a demonstration from :*


**A. B. MOULD & CONSTRUCTION CO., LTD.**

**VULCAN WORKS, VULCAN WAY  
NEW ADDINGTON, SURREY**

Telephone : Lodge Hill 2347

Telegrams : Abmould, Croydon

# Foundation cylinders by BRAITHWAITE



160 Braithwaite planted cylinders support the seaward section of the dry dock at Trieste, Italy. The barge mounted Braithwaite pile borer used for the project is also illustrated.

General Contractor: *Impresa Pietro Cidonio, Rome.*



## BRAITHWAITE FOUNDATIONS & CONSTRUCTION LIMITED

(Proprietors: Braithwaite & Co. Engineers Limited)


London Office:

DORLAND HOUSE • REGENT STREET • SW1

Telephone: WHitehall 3993

Telegrams: BROMKIRK PHONE LONDON. Telex: 23320





Circular tipping skips 3½ cu. ft. to 2 cu. yd.

# ABELSON for SKIPS



Special and non-standard skips manufactured to your specifications.



Circular controlled discharge bottom dump skips ½ cu. yd. to 1 cu. yd.

Roller skips ½ cu. yd. capacity.



Concrete pouring skip side discharge 10 cu. ft. to 27 cu. ft.



Box skips 3 cu. ft. to 7 cu. ft.



Concrete pouring skip bottom discharge 10 cu. ft. to 27 cu. ft.

Square handling or trenching skips 4-cu. ft. capacity.



**PIN YOUR FAITH  
TO THE TESTED  
BRAND**

THIS LABEL ON  
EVERY BARREL  
CARRIES WITH  
IT FIFTY YEARS'  
EXPERIENCE OF  
MANUFACTURE.

**NONE OTHER IS  
"JUST AS GOOD"**

**THE LEEDS OIL & GREASE CO.**

Phone 22480

LEEDS, 10

'Grams: "Grease."

# INSEPARABLE from REINFORCEMENT



## ... OF COURSE!

and a guarantee that  
the specified concrete cover  
is accurately maintained . . .

Complying in ALL respects to the British Standard & Codes of Practice. The U-KLIPON BAR SPACER of revolutionary design is instantly fixed with a vice-like grip in the desired position on all types of reinforcement, including mesh and prefabricated. As an inseparable part it positively cannot be displaced by heavy tamping or vibrating. For any Bar Spacing problem,

## CONSULT THE B.E.C. BAR SPACER SERVICE

which has been and is responsible for the most outstanding and prominent contribution to accurate bar spacing in reinforced concrete, thus providing precision, economy, and labour-saving means of ensuring that the specified concrete "cover" is maintained under all conditions. It is noteworthy that such is the increasing popularity and demand for "B.E.C." Bar Spacers, borne out by sales in excess of 35 millions, that we are able to RETAIN OUR PRICE LIST OF 1945 WITHOUT MODIFICATION. Over 120 stock sizes of bar spacers enable us to give immediate attention to requirements. Write now for comprehensive details and samples. Our Technical Consultants will call on request.

Patent Nos. 597,505, 715,563, 789,018, 818,538.

Registered Nos. 870,560, 886,239. English and foreign patents pending.



## B.E.C. BEARER BLOCK FOR GROUND BEAMS · BARREL ROOFING BRIDGES · MAT WORK · ETC.

The "B.E.C." precision-made bearer block is another inexpensive B.E.C. aid to obtain accuracy with speed in concrete construction. Let us send you full details.


Enhance your Prestige.  
Specify and use with  
confidence.

**BERRY'S ENGINEERING CO.**  
**SOLE MANUFACTURERS:**

Middle Road, Shoreham-by-Sea, Sussex

Phone and Grams: Shoreham-by-Sea 3541-2

CONTRACTORS TO MINISTRY OF SUPPLY, ETC., ETC.

**Architects :**

S. N. Cooke &amp; Partners

F./P.E.I.S.A.

**Main Contractors :**William Townson & Sons  
Ltd., Bolton.**Maxweld reinforces it**

The reinforcement fabric used in the Metal Box Company factory at Bolton was supplied by Richard Hill. Do you need reinforcements? Then call up the Maxweld man! He can give you all the facts on the type and quantity of fabric you'll need plus a rough idea of the cost. And he's backed by the

**Richard Hill Design Service**

who can then draw up more detailed plans and estimates. You can get him at Middlesbrough (2206), London (Mayfair 3636), Birmingham (Mid. 5625), Manchester (Central 1662), Leeds (2-7540), Bristol (24977), Glasgow (Central 2179), Nottingham (Bulwell 27-8383), Bournemouth (Westbourne 63491), Cardiff (46552), Belfast (29126).

**Maxweld fabric**

is manufactured by **RICHARD HILL LIMITED** (Established 1888)

Newport Wire and Rolling Mills, Middlesbrough, Yorkshire. Tel: Middlesbrough 2206

A MEMBER OF THE FIRTH CLEVELAND GROUP



CRC IT MX




A **RAWLPLUG** HEAVY DUTY FIXING DEVICE

# RAWLBOLTS

There is no waiting for cement to harden when you use Rawlbolts. The holes are drilled with a Rawltool to the exact size, the Rawlbolts dropped in and after the machine has been positioned the bolts are tightened. The expansion of the members locks the bolts in the holes. They cannot work loose through vibration or shock. The machine can be put into operation immediately.

Rawlbolts have earned a sterling reputation for strength and reliability throughout the world—they are used by the million every month. Rawlbolts grip by *expansion*—their strength as a fixing is based on the enormous compressive strength of concrete itself.









## RAWLBOLTS ARE MADE IN TWO TYPES

For fixing heavy machinery to floors there is the Loose Bolt type of Rawlbolt which enables the machine to be slid into position after the Rawlbolt has been inserted. For wall fixings use the Bolt Projecting type which will position the fixing before tightening up.




Please write for Chart and descriptive literature.

**Tools that save time.** For hole boring there is a big range of high efficiency Rawlplug tools for use by hand, electric and air power.

 <p><b>RAWLDRILLS</b> For hand boring for Rawlbolt sizes A to G.</p>	 <p><b>DURIUM MASONRY DRILLS</b> For use in hand and electric drills for Rawlbolt sizes C to G.</p>	 <p><b>DURIUM HAMMER DRILLS</b> For use in electric hammers for Rawlbolt sizes C to J.</p>
 <p><b>STARDRILLS</b> For hand boring for all Rawlbolt sizes.</p>	 <p><b>TRIFORM DRILLS</b> For use in electric hammers for Rawlbolt sizes C to K.</p>	 <p><b>P. H. BITS</b> For use in pneumatic hammers for Rawlbolt sizes E to K.</p>

B345A

**RAWLPLUG CO. LTD., CROMWELL RD., LONDON, S.W.7.** The World's Largest Manufacturers of Fixing Devices



An Electrically Driven PC3 Concrete Pump with remixer. Capacities from 20 to 24 cu. yds. per hour. Ranges actually obtained 135 ft. vertical or 1,500 ft. horizontal. Also smaller model PC4—8-10 cu. yds. per hour.

**EFFICIENT RECONDITIONING SERVICE**

## **CONCRETE BY PUMP AND PIPELINE**

- The most efficient method of placing concrete.
- Life of Pump practically indefinite: all essential surfaces in contact with concrete are renewable.
- Pumpable concrete must of necessity be good concrete.
- Pump and Mixing Plant can be located at the most convenient position within the pumping range.
- The continuous output of the Pump at a constant speed governs the working of the whole concreting gang.

THE REGISTERED TRADE MARK OF

**PUMPCRET**

THE CONCRETE PUMP COMPANY LIMITED

# **THE CONCRETE PUMP COMPANY LTD**

**4 STAFFORD TERRACE, LONDON, W.8**

Telephone: Western 3546

Telegrams: Pumpcret, Kens, London

means 2

MACALLOY

## NEW SAFETY

Macalloy high tensile steel bars, as used in the Lee-McCall system, set a new standard of safety and reliability in the prestressing of concrete.

Positive and accurate securing of drilled end plates. Rolled threads give positive anchorage, without slip.

The jacking equipment enables measurement of the extension to be made easily and accurately, and the force used can readily be checked on a large easily-read gauge.

Stressed tendons with rolled thread anchorages can be checked for stress right up to the time of grouting and, if necessary, re-stressed.

The large-diameter Macalloy bars are more resistant to corrosion than mild steel; exposed bars can be given first-class protection.

These and many other points of superiority make 'Macalloy' bars the most economical, simple, reliable and practical system of prestressing.

### McCALLS MACALLOY LIMITED

TEMPLEBOROUGH • SHEFFIELD • P.O. BOX 41

Telephone: ROTHERHAM 2876 (P.B. Ex 8 lines)

LONDON: SLOANE 8428    PORTSMOUTH: COSHAM 78782  
BIRMINGHAM: ACOCKS GREEN 8229

**PRESTRESSING**  
by **McCALLS**

McCALL & CO. (SHEFFIELD) LTD.

McCALLS MACALLOY LTD.

PRECISION ROOFS LTD.

McCALLS MACALLOY AFRICA (PROPRIETARY) LTD.


McCALLS MACALLOY (AUSTRALIA) PTY. LTD.

McCALLS MACALLOY (CANADA) LTD.

ONE...



**TWO!**



## 'STABIL' BINDERS

## ARE GREAT LABOUR SAVERS


In one simple action they fix reinforcing rods as though welded. No slipping. No "fiddling" with wire. No tools to get mislaid. Any workman can use them. Made in all sizes for binding  $\frac{1}{2}$ -inch up to  $1\frac{1}{2}$ -inch rods. Give "Stabil" Binders a trial and judge for yourself.

● **SEND TO-DAY** for demonstration samples and prices.

**HUNTLEY & SPARKS LTD**

DEBURGH RD., 5. WIMBLEDON, S.W.19

**Phone: Liberty 2446**



## Trent Gravels

Washed & Crushed  $1\frac{1}{4}$  in. to  $\frac{1}{2}$  in.

We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt deliveries guaranteed and keen competitive prices quoted. Send for samples and prices.

**TRENT GRAVELS LTD**

## ATTENBOROUGH

Telephone : Boston 5-4253

## MOTTS

## "THE CONCRETE YEAR BOOK"

1960 EDITION

1288 pages

Price 10s. : by post 11s. 9d.

\$2.40 in Canada and U.S.A.

## HANDBOOK

In this Section no attempt is made at giving individual opinions, but to present in concise and convenient form specifications or methods which are either standard practice or recommendations formulated after thorough investigations by competent bodies. Complete memoranda and data of everyday use.

## DIRECTORY

The only complete Directory of the concrete industry, classified under different headings for ease of reference. Complete list of trade names and brands.

## CATALOGUE

Describes the businesses or products of more than 900 firms connected with or catering for the concrete industry. Invaluable to anyone seeking a firm of contractors to carry out special kinds of work, or a machine, material or product for any purpose.

**Make sure of your copy now.**

**CONCRETE PUBLICATIONS LTD.,**  
14 DARTMOUTH STREET,  
LONDON, S.W.1

THE NEW

**MILLS**

# LIGHTWEIGHT pecco-beam

## ALL-STEEL HORIZONTAL SHORING



### GIVES CLEAR SPANS FROM 9' 6" TO 21' 2"

- Proven Safety Factor: Minimum of 2:1
- Only two basic parts—easy to erect, store and transport
- No propping—kindred trades can work freely below
- Keeps costs down. High load capacity enables larger areas to be shuttered with fewer shores
- Rolled-in camber ensures level slab under load
- Demonstrations arranged
- Immediate delivery from nearest MILLS depot
- Free planning service

For larger spans and greater load-bearing capacity, use the Standard pecco-beam

For leaflets containing loading tables and full details of Lightweight and Standard PECCO-BEAMS get in touch with your nearest Mills depot.

**MILLS SCAFFOLD CO. LTD.** (A subsidiary of *Guesst, Keen & Nettelfolds, Ltd.*)

*Head Office:* Trussley Works, Hammersmith Grove, London W.6 (Riverside 3011).  
*Depots:* BIRMINGHAM • BOURNEMOUTH • BRADFORD • BRIGHTON • BRISTOL • CANTERBURY • CARDIFF  
 COVENTRY • CROYDON • GLASGOW • HASTINGS • HULL • ILFORD • LIVERPOOL • LONDON  
 MANCHESTER • MIDDLEBROUGH • NEWCASTLE • NOTTINGHAM • OXFORD • PLYMOUTH • PORTSMOUTH  
 PRESTON • READING • BOTHERHAM • SOUTHAMPTON • SWANSEA

THERE'S NO LIMIT TO THE SUPPORT YOU CAN GET FROM

**MILLS**

**CONCRETE  
PROOFING  
Co. LTD.**

**GUNITE  
SPECIALISTS**

Expert advice and schemes submitted for gunite work of every kind. Complete information on the various uses of gunite will be gladly sent on request

116 Richmond Road, Kingston-upon-Thames, Surrey. Telephone: KINGSTON 7883 and 9252

## **COPPER STRIPS** for expansion joints

All Reinforced Concrete Engineers recognise the advantages of using copper strips for sealing joints in concrete work. Copper is ductile, will not crack under repeated bending, is non-corrosive and is unaffected by wet concrete. We specialise in the supply of perforated copper strips of all required lengths and widths for expansion joints, and shall be pleased to submit prices against detailed specification.




**ALEX J. CHEETHAM LTD.**

MORTON STREET • FAIRSWORTH • MANCHESTER

Telephone: FAIRSWORTH 1115/6

DS.14





Tel.: UXBRIDGE  
3399

# T.P.S. SHUTTERING and MOULD PAINTS

will make your shuttering and moulds last longer,  
often save the labour costs of repeated mould oil  
application, and are also the cheapest alkali  
primers for general use under paint work

*Reduced costs and clean concrete surfaces are always obtained from shutters and  
moulds treated with these paints. Wood grain is filled and sealed against water and  
alkali. Douglas Fir staining eliminated*

Ask for the type for YOUR purpose


**SPECIAL TYPES FOR PLYWOOD,  
STEEL OR CONCRETE SURFACES  
TO SUIT ALL REQUIREMENTS**

PROMPT DELIVERY FROM STOCK !

**TECHNICAL PAINT SERVICES, DEPT. C.G.E.**

THE PAINT CENTRE — UXBRIDGE — MIDDLESEX

FOR CONCRETE PRODUCTS


**RANALAH****STEEL  
MOULDS**CUT CAPITAL COSTS  
BETTER CASTS & MORE  
CASTS PER MOULDGARAGES, COAL BUNKERS, CILLS,  
COPING STONES, AGRICULTURAL AND  
INDUSTRIAL BUILDINGS FENCING POSTS,  
KERBS, GARDEN EDGINGS, ETC.**RANALAH STEEL MOULDS LTD**

LOWER BEVEDEAN

BRIGHTON

SUSSEX TEL 62216-78

**CONCRETE ROADS FIRST**  
because  
**CONCRETE ROADS LAST**



A.A. NARBOROUGH

**REINFORCEMENT**

**by McCALLS**

**McCALL & COMPANY (SHEFFIELD) LIMITED**

**TEMPLEBOROUGH • SHEFFIELD • P.O. BOX 41**

Telephone: ROTHERHAM 2076 (P.B. Ex. 8 lines)

**LONDON: SLOANE 9428**

**PORTSMOUTH: COSHAM 78702**

**BIRMINGHAM: ACOCKS GREEN 0229**

**NEWCASTLE: 38793**

McCALL & COMPANY (SHEFFIELD) LIMITED

McCALLS MACALLOY AFRICA (PROPRIETARY) LIMITED

McCALLS MACALLOY LIMITED

McCALLS MACALLOY (AUSTRALIA) PTY. LIMITED

PRECISION ROOPS LIMITED

McCALLS MACALLOY (CANADA) LIMITED

# "COL-O-ROCK"

Registered Trade Mark

## EXPOSED-AGGREGATE PANELS

by

### J. A. KING & CO., LTD

*Write or Phone*

181 Queen Victoria St., LONDON, E.C.4

Telephone: CENTRAL 5866 (5 lines)

Telegrams: Kinovique Cent London



## BOLTS & NUTS

## TIE-RODS

ETC.

**FOR THE CONTRACTOR**



*Manufactured by*

**B. PRIEST & SONS LTD**
OLD HILL STAFFS ENG

PHONES LEADLEY WELTH 4222 B 0-4 4226

## Precision in Concrete Cover...



*Write Now!*

for fully  
illustrated  
brochure

A revolutionary economy  
for lightness, speed of  
handling, and range of  
application—for reinforcing  
bars in concrete.

with



PATENTED. Regd. Design 893503.

Plastic Distance Pieces

**Samuel & Son (moulders) Ltd**

WREN MILL, CHADDERTON, LANCs. Sales Office: Tel: Manchester DEA 4671/2  
Sole Manufacturers and Distributors of ABIT pk Plastic Distance pieces (A.B.  
ABERG No. 31269/58) in Great Britain, The Commonwealth and Eire.

# “COL-O-ROCK”

Registered Trade Mark

## EXPOSED-AGGREGATE PANELS

by

# J. A. KING & Co., LTD

*Write or Phone*

181 Queen Victoria St., LONDON, E.C.4

Telephone: CENTRAL 5866 (5 lines)

Telegrams: Kinovique Cent London



## BOLTS & NUTS

## TIE-RODS

ETC.

**FOR THE CONTRACTOR**



*Manufactured by*

## B. PRIEST & SONS LTD

OLD HILL STAFFS ENG

PHONE: CRADLEY HEATH 6227 9-14 6120



## Precision in Concrete Cover...



for fully  
illustrated  
brochure

A revolutionary economy  
for lightness, speed of  
handling, and range of  
application—for reinforcing  
bars in concrete.

with




PATENTED. Regd. Design 893503.

Plastic Distance Pieces


### **Samuel & Son (moulders) Ltd**

WREN MILL, CHADDERTON, LANCs. Sales Office: Tel: Manchester DEA 4671/2  
Sole Manufacturers and Distributors of ABIT *ph* Plastic Distance pieces (A.B.  
ADERG No. 31269/58) in Great Britain, The Commonwealth and Eire.



## First time in Britain

*Swiss BBRV prestressing used  
on Isle of Grain Bridge*



The cable bridge at the Isle of Grain is 232 ft. 3 ins. long, with two clear spans of 90 ft. and one of 30 ft. The Swiss BBRV system of prestressing concrete was used for these spans. This system is unique in that each wire is anchored by upsetting its end to form a nail head which bears on the face of a special anchor head. The individual wires are grouped into cables with a common anchor head and stressed with one jacking operation.

Further details of this project are available on request.

*Sponsor:* South Eastern Gas Board.


*Design:* S.E.G.B. Construction Department in collaboration with Simon-Carves Ltd.

*Contractors:* Sir Robert McAlpine & Sons Ltd.

Johnson's were in at the start with wire for prestressed concrete, having worked with designers throughout the development of prestressing techniques. Johnson's wire gained and maintains its lead by reason of proper quality control and the most efficient customer-service in the industry.

**wire was essential -**

***Johnson's***  
**of course!**



**ISLE OF GRAIN  
BRADWELL  
GATWICK**

At the Isle of Grain Refinery for the British Petroleum Company Limited, Bradwell Nuclear Power Station and Gatwick Airport, Sternson No. 610 was used.

Sternson No. 610 is the obvious choice. Not only for bonding granolithic topping but for ensuring watertight construction joints. And the bonding

of heavy renderings to concrete surface without hacking.

Used on many Government Contracts at home and overseas, in the multi-storey John Lewis Building in Oxford Street, in Bowater House, the Walls Depot at Acton . . . The list is almost endless. Using Sternson No. 610 puts you in good company.

**CONCRETE BONDED WITH** *"Sternson"*  
**610**


**SBD**  
**STUART & DICKENS LTD.**

For complete information, write :—  
Manor Way, Boreham Wood, Herts.  
Telephone : Elstree 2211.

LENSCRETE LTD

## maximum light minimum cost


LITEX roof lights give a very high transmission of light—up to 92%—and are easily and quickly handled and fitted. A full range of standard form metal ventilators, curbs and liners are available for use with LITEX roof lights.



LITEX spherical roof lights


## Litex LAMINATED FIBREGLASS roof lights

LITEX roof lights with their glass fibre reinforced construction can be used with advantage in many places where conventional lights would be impracticable or too costly. Virtually unbreakable, heavy packing is unnecessary allowing quick and easy handling on site.



LITEX rectangular roof lights

LITEX roof lights are ideal for use in schools, hospitals and other buildings where absolute safety is required—they will not shatter and cannot support combustion. The plastic will not creep, nor become brittle with age or very hot temperatures.



LITEX lantern lights

LITEX roof lights are not attacked by smoke or fumes from most industrial processes, and may safely be used in factory and workshop buildings.

For further information about LITEX roof lights please write to

LENSCRETE LIMITED Queens Circus London SW8 telephone MACaulay 1063

## Underpinning by Pynford



Illustration shows stooing under heavy brick piers, prior to fixing reinforcement. R.C. frames can be founded under buildings large and small using PYNFORD stools.

- \* SITE INVESTIGATIONS that are clear and to the point.
- \* NEW FOUNDATIONS designed and/or constructed to suit all site conditions.
- \* UNDERPINNING by the proved **Pynford method** for high-level beams, or below ground level.
- \* JACKING Re-levelling existing buildings and cheap provisions for new buildings.
- \* EXCAVATING SHIELDS supplied for digging to any depth through shifting ground such as sand mixed with water.

**Foundation Engineers, Site Investigations, Underpinning, Jacking**

# Pynford Limited

Patentees

74 LANCASTER ROAD, STROUD GREEN, LONDON, N.4

Telephone: ARChway 6216-7



## On the subject of PIPES, moulds and equipment . . .



As manufacturers of all types of steel moulds and formwork for precast and in-situ concrete production, we welcome your enquiries in this specialised field.

If required our experienced staff will plan a comprehensive scheme for the manufacture of your precast units on site.

# Coneybeare

THE ORIGINAL PIPE MOULDS

CONEYBEARE & CO. LTD., 89-91 Greenwich Church St., London S.E.10 Tel: Greenwich 0821

---

## WELBECK TRADING Co. (London) Ltd

WELBECK HOUSE, 2-6 BACHES STREET, CITY ROAD, LONDON, N.1

Telephone: CLerkenwell 4373 (PBX)

Telex: 23712

## STEEL REINFORCEMENT MANUFACTURERS

$\frac{3}{16}$ " to  $\frac{3}{8}$ " DIAMETER ROUNDS

Cut to dead lengths a speciality

No extra for cut lengths over 5 feet

Banding if required

Write or telephone your requirements


SPECIAL OFFER FOR DELIVERY IN  
FEBRUARY OR MARCH

in mills lengths to your own requirements up to 40 ft.:-

100 tons  $\frac{3}{16}$ " diameter

100 tons  $\frac{1}{2}$ " diameter

50 tons  $\frac{3}{4}$ " diameter



# Testing concrete cubes on site


## MILBANK-WELLS

### HYDRAULIC PRESS AND CUBE MOULDS

Immediate Delivery

Two Sizes : 4 in. and 6 in.

PRESSES and CUBE MOULDS  
Testing to 16,000 lb. per sq. in. to  
B.S. 1881.



Approved for  
all Government  
Contracts

IN USE  
ALL OVER  
THE WORLD

6-IN. PRESS  
258 TONS

**£258**

4-IN. PRESS  
110 TONS

**£125**

## MILBANK FLOORS LTD

### PRESTRESSED CONCRETE CONSTRUCTION

RIVER HOUSE, EARLS COLNE, ESSEX

Telephone: Earls Colne 410



## PRESTRESSED

### FLOORS & ROOFS FRAME BUILDINGS


SPANS UP TO 40 ft.  
ALL TYPES



THE MOST ADAPTABLE FRAME BUILDING  
FOR INDUSTRY AND AGRICULTURE

SINGLE SPAN · MULTI SPAN · CANTILEVER





## POWER for industry

Our range of industrial engines are a practical proposition for many types of industrial equipment... compressors, cranes, pumps, contracting equipment, earth borers, generators, railcars, welding plant, works trucks, tractors and conversions. Simple design, modern flow-line production methods and common interchangeable parts contribute to the low cost of these high efficiency engines. And remember, every engine is fully backed by a World-wide Parts and Service Organi-

sation. Take your choice from a wide power range... Diesel 20 to 86 b.h.p. and Petrol 11 to 87 b.h.p. (12-hr. rating).

**DIESEL ECONOMY**—have you considered the replacement of existing power units in your equipment and trucks with the famous 4D Diesel engine? You'll have the unique advantages of economy, long-life and low running costs... plus the best service in the World!

Wherever you are, whatever your problem.



**MOTOR COMPANY LIMITED  
ENGLAND**

are at your service

For further details of our

## INDUSTRIAL ENGINES

and the equipment they power,  
send the coupon to your nearest Ford Dealer  
or direct to

FORD MOTOR COMPANY LIMITED · PARTS DIVISION (S51) · AVELLY DEPOT · SOUTH OCKENON · BOMFORD · ESSEX · ENGLAND

Please send me technical brochures of your  
\*PETROL/DIESEL Industrial Engines. The  
maximum B.H.P. required is.....at.....  
R.P.M. Also, please send details of the follow-  
ing equipment powered by your engines.

Name .....

Address .....

Nature of Business .....

Telephone No. ....

\* Delete where not applicable

G51-23-2

# BRITISH VISQUEEN

*make a No.*

# 1

*choice*



The new British Visqueen factory at Stevenage was built to produce the largest output of polythene sheeting in Europe; and it is here that the Visqueen Building sheet is also manufactured to supply an increasing number of applications for it in the building industry.

To render the concrete factory floors hard, dustless, waterproof and able to withstand exceptionally heavy wear and tear, British Visqueen chose Lillington's No. 1 Metallic Liquid.

For nearly fifty years, architects have specified Lillington's No. 1 Metallic Liquid, the scientifically prepared admixture that renders concrete completely waterproof and dustless and accelerates setting time.

*No. 1 Metallic Liquid is a necessity for waterproofing cement renderings to walls and basements, in mass concrete retaining walls, foundations, flat roofs and tanks. You can rely on it to give complete satisfaction because IT IS THE ONLY PROOFER SOLD UNDER GUARANTEE.*

LILLINGTON'S

## **No. 1 Metallic Liquid**

From **5/-** per gallon

Special terms for  
bulk contracts

Write for Booklet 56

ALL OUR PRODUCTS NOW SOLD IN FREE CONTAINERS

### **GEORGE LILLINGTON & CO. LTD**


Willow Lane, Mitcham, Surrey. Tel: Mitcham 1066. For Scotland: 42 High Street, Greenock AP/339A

# DEEP MINE CONCRETING SIMPLIFIED

**COLCRETE  
INJECTED  
CONCRETE**

At South African Gold Mines the concrete linings of tunnels, pump chambers and the construction of shaft sumps have been simplified by using uncrushed rock spoil injected with COLGROUT mixed at surface and passed down shafts up to 6,000 ft. deep through 1½" pipes.

Contractors : The Cementation Company (Africa) (Pty.) Limited.



COLGROUT mixing plant at a South African Gold Mine.



A station cross cut 6,000 ft. below surface, lined with Colcrete constructed from surface.



The main pump chamber of a South African Gold Mine 6,000 ft. below surface and lined with Colcrete.

**Colcrete methods can solve  
many Concreting Problems**

## COLCRETE LIMITED

STROOD • ROCHESTER • KENT

Phone Strood 78431/2/3. Grams : Groutcrete, Rochester

**WATERTIGHT  
LININGS  
FOR  
RESERVOIRS,  
SWIMMING  
POOLS, ETC.**



**LININGS  
FOR  
TUNNELS,  
SEWERS,  
TANKS.**

*Specialists in the Repair and Reconditioning of  
Reinforced Concrete Structures, etc.*

THE

**GUNITE**  
CONSTRUCTION CO. LTD  
WESTERN HOUSE, HITCHIN, HERTS.

Telegrams :  
Gunite  
Hitchin

Telephone :  
Hitchin  
4871

**Best Quality  
CONCRETE  
AGGREGATES**  
*in all grades*

DELIVERED BY ROAD OR RAIL

**WM. BOYER  
& SONS LTD**

MEMBERS OF S. & G.A. of G.B.

ESTABLISHED 1810

IRONGATE WHARF, PADDINGTON, W2


TELEPHONE : PADDINGTON 2034-4

**TABLES FOR THE DESIGN OF BEAMS AND  
SLABS ACCORDING TO B.S. CODE OF PRACTICE  
No. 114, 1957**

In response to many requests, the article and tables by Mr. Jacques S. Cohen, in this journal for August, 1957, have been reprinted together with an additional table. These tables enable any rectangular section to be quickly designed by both the elastic method and the load-factor method, and the relative economy of the results of each method of design can be seen at a glance. The price of the reprint is 4s. (4s. 3d. by post); 1 dollar in Canada and the U.S.A.

CONCRETE PUBLICATIONS, LTD., 14 Dartmouth Street, London, S.W.1

# Bridge Bearings by **WESTWOODS**



Universal Bearings to support 250 tons, allowing for horizontal movement in all directions, and also vertical adjustment. The illustration shows two Bearings, one with grease casings removed.

## **JOSEPH WESTWOOD & CO. LTD.**

Contractors to H.M. Government Departments, Crown Agents for the Colonies, British Railways (British Transport Commission) etc. etc. Bridge and Constructional Engineers, Manufacturers of Mechanical Grabs, Pressed Steel Troughing and Sheet Metal Equipment. Steel Stock Holders.

**NAPIER YARD, MILLWALL, LONDON, E.14** Phone: EASt 1043

Cables: Westwood, London. Telegrams: Eastphone, London

# *Steel Reinforcement*

A complete service of  
Design, Fabrication and  
Fixing of Steel Rein-  
forcement for all types  
of Reinforced Concrete  
Construction.

M.S. Bars to B.S.S. 785, bent,  
bundled and labelled, delivered to site  
ready for fixing. No loss of time in  
checking and sorting material. No  
loss of material due to prolonged  
storage on site.

## **T. C. JONES**

AND COMPANY LIMITED

### **REINFORCEMENT ENGINEERS**

17 BUCKINGHAM PALACE GARDENS  
LONDON, S.W.1 Tel: SLOane 6271

Head Office: Wood Lane, London, W.12

Tel: Shepherds Bush 2828


South Wales Office: Bute Street, Cardiff

Tel: 25786

Works: Shepherds Bush, London, Neasden, Middx.  
Trowerby, Glam.







333 Simplex Cast-in-situ Concrete Piles were used in the foundations of the Municipal College Extensions in Anglesey Road, Portsmouth

Architect to the City of Portsmouth: F. Mellor, Esq., F.R.I.B.A.

## **SIMPLEX CONCRETE PILES LTD.**

190 PALACE CHAMBERS,

BRIDGE STREET,

WESTMINSTER, S.W.1

Telephone: Trafalgar 1167-9

# EXAMPLES OF THE DESIGN OF REINFORCED CONCRETE BUILDINGS

IN ACCORDANCE WITH THE BRITISH STANDARD CODES

By Chas. E. Reynolds, B.Sc., M.I.C.E.

SECOND EDITION

1959

All recommendations relating to design in the

**REVISED B.S. CODE NO. 114 (1957)**

**"Structural Use of Normal Reinforced Concrete  
in Buildings"**

and other relevant codes are considered and applied to the design  
of all parts of a building.

Alternative designs of floors, flat slabs, roofs, and columns.

Complete data in connection with the

**LOAD-FACTOR METHOD**

of the design of slabs, beams and columns subjected to bending.

OVER 50 DESIGN TABLES

TWENTY-FOUR SHEETS OF CALCULATIONS

SEVENTEEN FULL-PAGE DETAIL DRAWINGS

and numerous other illustrations and diagrams

TO AID DESIGN

A "CONCRETE SERIES" BOOK

## ORDER FORM

To  
CONCRETE PUBLICATIONS, LTD.  
14 DARTMOUTH STREET,  
LONDON, S.W.1, England.

Please send.....copy (copies) of

"Examples of the Design of  
Reinforced Concrete Buildings."

Price 12s. 6d.; 13s. 8d. by post.  
3 dollars in Canada and U.S.A.

A remittance for.....is enclosed.

## BLOCK CAPITALS PLEASE

NAME .....

ADDRESS .....

.....

.....

Remittances from Canada and U.S.A.  
may be made in the ordinary way by draw-  
ing a check on the customer's bank made  
payable to Concrete Publications, Ltd., in  
dollars or by International Money Order.



# TRILLOR ELECTRIC EXTERNAL VIBRATORS



**pecially designed  
for very dry mixes  
for in situ and  
precast concrete**


This High Frequency Vibrator is available in eight sizes, most of which are equipped with quick-release attachment fittings, which enable them to be used with the highest vibrating efficiency for all types of steel and wooden shuttering and moulds. If required, surface plates or pans can be fitted for surface vibration.

**E · P · ALLAM & CO. LTD.**

**LONDON: 132-135 Sloane Street, S.W.1. • Telephone: Sloane 9976 (5 lines)**

**Works: Southend-on-Sea Tel.: Eastwood 335243**

**AGENTS & DISTRIBUTORS:** Strangford Ltd., Belfast and Dublin; A. Gunn & Co. Ltd., Nitrincham, Ches.; O. L. Davies Ltd., Port Talbot, Glam.; J. Lewis (Machinery) Ltd., Burslem, Stoke-on-Trent; G. B. Corner & Son, Leeds and Nottingham; John Raulstone Ltd., Newcastle-on-Tyne; W. R. Selwood, Ltd., Chandler's Ford, Southampton; J. A. McAlra & Co. Ltd., Glasgow



## FOR HANDLING CEMENT IN BULK

P15 PORTASILO working on the construction of Wilmslow Grammar School, Cheshire.  
Contractors: L. Brown & Sons Ltd. Wilmslow

- ✱ Fully proved on thousands of sites
- ✱ A range to suit all Concrete Mixers
- ✱ No condensation problems
- ✱ Backed by a first class after sales service
- ✱ Fully automatic, remote push button control provided by the addition of the Portasilo 'Autofeed' which can be interchanged between Portasilos as required
- ✱ FOR SALE OR HIRE

### PORTASILO LIMITED

CONTRACTORS PLANT DIVISION, COMBINATION ROAD, PARK ROYAL, LONDON N.W. 10

Telephones: ELGAR 6214 - 6215 - 3726

HEAD OFFICE: YORK

AND AT BIRMINGHAM, MANCHESTER, GLASGOW, BRISTOL, BELFAST AND DUBLIN



Write or phone today for details of full range of 11, 15, 20 and 30 ton capacity models or ask for a representative to call

# CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

Volume LV, No. 2.

LONDON, FEBRUARY, 1960.

## EDITORIAL NOTES

### A Code for Prestressed Concrete in Buildings.

ON occasion, the view has been expressed in these notes that codes should embody only practice that has proved to be sound and, by inference, premature publication of recommendations which have not stood the test of time must be avoided. In this respect, the British Standards Institution has done well, since it has not previously rushed into print with a code containing recommendations for the use of prestressed concrete in buildings but has waited nearly two decades after the general introduction of prestressed concrete into this country before publishing its code of practice.\* So many prestressed concrete structures have now been built in this country with so many systems, and so many engineers have now obtained experience, successful and otherwise, that the publication of such a code is timely. As is to be expected, the Code owes much to the "First Report on Prestressed Concrete" issued by the Institution of Structural Engineers in 1951 which, though well received at the time, may be considered to correspond to the provisional recommendations issued in Germany in 1953 and the tentative recommendations published in the U.S.A. in 1958.

The technical recommendations contained in the Code should, in the main, be acceptable to most practising engineers. We would, however, criticise the assumption that prestressed concrete designs are entrusted only to "chartered structural or civil engineers experienced in the use of concrete" because, in the first place, many eminent foreign engineers and others would be excluded, and secondly, the design of prestressed concrete is specialised and fraught with problems to deal with which a practitioner in ordinary reinforced concrete may not have had the necessary experience. Also, it is unfortunate that the notation which is becoming standardised because of its inclusion in the code for reinforced concrete buildings is not adopted in all cases where applicable. It is regretted that some of the terminology will do much to perpetuate some words to which are given meanings other than their true meanings. An example is "loss" of prestress when reduction of the effective prestressing force is meant, since the

\* British Standard Code of Practice, CP.115 (1959): "The Structural Use of Prestressed Concrete in Buildings". (British Standards Institution. Price 8s. 6d.)

compressive force imposed on a member is not always lost but, due to friction and some other causes, may be distributed differently. We have expressed previously our views on the term "tendon" to describe prestressing steel of all kinds; the result of our competition for a more appropriate word to describe these components is given on page 71.

The foregoing are perhaps small matters in a document that, with few notable exceptions, deals adequately with those aspects of prestressed concrete on which a designer requires guidance. A review of the recommended stresses and a comparison with German and American practice are given on page 73. One recommendation calling for comment is that there is no limit to the principal tensile stress due to the combination of the effects of prestressing, bending, and shearing so long as reinforcement is provided to resist the entire shearing force. This omission is so contrary to practice in reinforced concrete in this country that, without adequate explanation, it is questionable and may lead to defective design in the hands of those not fully conversant with prestressed concrete. Another omission, in our view, is the failure of the Code to describe the "recognised general principles relating to the design of prestressed concrete", and to give the basic formulæ. Where else than in a code of practice, and especially in the first in this country, would an engineer expect to find such principles? Even in the code for reinforced concrete the basic principles are described, although these have been known for upwards of fifty years, and the formulæ for the load-factor method are given.

The Code does deal, however, in a useful manner with the method of calculating the strength of beams at incipient failure, and comprehensively with the reduction of the prestress due to friction and some other causes. The reduction coefficients cover a wide range but apply only to normal conditions and known materials. Coefficients for exceptional conditions and new processes can be established by test. It may be thought that some of the coefficients are slightly high, but in a general recommendation this is as it should be. There is nothing to prevent, and much in favour of, an engineer making tests to determine coefficients which may be more applicable to the materials and equipment it is proposed to use. The stiffness of a metal sheath may affect considerably the frictional resistance, and there is likely to be some reduction of prestress due to friction between the wires in a group of wires forming a curved cable if all the wires are not tensioned at the same time; these potential causes of reduction are not mentioned in the Code, nor are recommendations given relating to such factors as the reduction of effective force due to the rope-tightening effect in strands, that is wire ropes, or the effect of torque due to the lay of the wires in ropes. Although wire ropes, which are by no means a novelty today, are included in the prestressing steels permitted, there are no further references thereto, not even in the clause dealing with the permissible stresses in the prestressing steel; in fact this clause deals with two only out of the several permitted forms of "tendon".

The recommendations regarding anchoring the prestressing steel in post-tensioned members should be amplified. Although it is stated that the anchors should be capable of maintaining the prestressing force under the most adverse conditions of loading, no margin of safety is expressed for the strength and other properties of the anchoring devices, and it may be that these devices may therefore



constitute the weakest part of the construction. It is also stated that the principal tensile stress in the concrete due to the anchors should be "minimised" and that reinforcement may be necessary to resist such stresses; but no recommendations are given concerning what stress is allowable with or without reinforcement, nor what local compressive stress due to the anchors is permissible as is given in some other codes. It is to be expected that a code would be much more explicit on the design of the ends of beams in view of the fact that experience shows this part to be so vulnerable.

Among more secondary matters, mention might be made of the casual reference to statically-indeterminate structures; the omission of guidance to the reduction of the stresses in a beam when the ratio of length to breadth exceeds thirty, and likewise what modification is required if the ratio of depth to breadth exceeds two-and-a-half; the loading due to wind and snow is classified as being of short duration, but this may be far from true in the case of snow; and the note relating to the consideration of the effect of the reduction of prestress on the compressive stresses at transfer which seems to be more applicable to the tensile stresses in the concrete.

It is, of course, easy to criticise a first attempt as this Code is, and no doubt many matters, including some of those in the foregoing, will be given attention when the Code is revised. Since it is likely that revision will not take place for several years, it may be worth while for the Institution to issue in the near future a short memorandum giving supplementary recommendations on some matters; a precedent for this procedure is the memorandum issued at one time in connection with the by-laws of the London County Council for reinforced concrete.

### **"A Word is Wanted"—Result of Competition.**

MANY entries were received from many countries in the competition, announced in this journal for September last, for a word to describe the tensioned steel or other material or means used to prestress concrete. The assessor has awarded the prize of £25 to Mr. Paul L. Sowerby, of West Didsbury, Manchester, for the word **STRICTOR**. In our next number we propose to give the assessor's report and some of the other words submitted.

### **The Use of English.**

READERS of this journal who are in agreement with the opinions expressed in some of our Editorial Notes in which the lack of accuracy of expression in the writings of engineers is deplored, will be pleased with the suggested revised requirements for entry to the Universities of Oxford and Cambridge, since it is proposed to include a compulsory paper on "the use of English". The report issued by Oxford states: "We think that there will be wide agreement that far too high a proportion of undergraduates at the time of their matriculation find undue difficulty in expressing themselves clearly and accurately in their own language". The report issued by Cambridge contains a similar condemnation of the present system which results in a low standard of English writing among so many undergraduates.

## Book Reviews.

**"Advanced Structural Design."** By C. S. Benson. (London: B. T. Batsford, Ltd. 1959. Price 50s.)

This is an unusual book in that, without preamble or explanation, full calculations and some details are given for the design of complete structures including a trough-shape coal bunker, a water tower, a grain silo, an office building, and the foundation of a retort house in reinforced concrete. Steel structures include a coal bunker in a boiler house, a water tower, a road bridge of 75 ft. span, a pump-house, a shed 120 ft. wide, a two-bay frame, a garage with a north-light roof, a theatre balcony, a crane gantry, and a signal gantry. A brick chimney and vaults with brick arches are included.

The jargon and contractions common in design offices are used, and may present some difficulty to inexperienced readers for whom the book is evidently intended in spite of the word "advanced" in the title. Also it may not always be clear which formula is being used since in many cases numerical substitution is made without identifying the general expression. On the other hand, in some instances the full derivation of a formula is given. In general the detailing is good, although exception may be taken in some cases; for example, the absence of horizontal bars in the lower part of the wall of a square tank and the general complicated nature of this particular detail.

In each example the design relates to a structure of specified dimensions; the planning of the structure and its supports is not described. The design finishes at the stage when the calculations and sketches would be passed to a designer-draftsman to prepare the working drawings; the book would be improved by including some drawings of this nature, especially for the reinforced concrete structures.

**"Surveying."** By A. Bannister and S. Raymond. (London: Sir Isaac Pitman & Sons, Ltd. 1959. Price 45s.)

The principles of land and hydrographic surveying are dealt with in detail in the four hundred pages comprising this book, in which numerous examples are given. The construction and operation of instruments in common use, and some which have been developed recently, are described. The book is intended primarily

for students preparing for professional examinations, but many bibliographical references to sources of more detailed or advanced information are given. Some particulars of field astronomy are given. Among the modern methods of surveying is the measurement of distances by reflected light or radio waves. The chapter dealing with various methods of photographic surveying includes stereoscopic aerial photography.

**"The St. Lawrence Seaway."** By T. L. Hills. (London: Methuen & Co., Ltd. 1959. Price 12s. 6d.)

A GENERAL account is given of the development and construction of the navigable waterway from Montreal to the Great Lakes, and a description in non-technical language of the organisation and carrying out of the extensive civil engineering works is included. These works comprise many large concrete structures such as the Long Sault dam, an arched gravity structure about 2900 ft. long and having a maximum height of 145 ft., and the Iroquois dam, a buttress gravity structure 2540 ft. long and 67 ft. high.

**"Der Stahlhochbau."** Volume II. By C. Kersten and Werner Tramitz. (Berlin: Wilhelm Ernst & Sohn. 1959. Price 29.60 D.M.)

IN this sixth edition of the second volume of the late C. Kersten's guide for students and practising engineers on structural steelwork in buildings there are chapters on frames, cantilever construction, light-weight buildings, lattice-roof girders, buildings of large span, crane beams, roof coverings, roof-lights, glazing, windows, doors, and gates. The importance of correct constructional details is emphasised and is illustrated by more than five hundred diagrams. There are numerous fully-worked examples.

**"Technischer Strahlenschutz."** By Thomas Jaeger. (Munich: Karl Thiemeig. Price not stated.)

THE subject is high-density concrete for shielding atomic power plants and the disposal of radioactive wastes. The book is based upon research in the U.S.A. and Great Britain.

## Book Received.

**"Sculpture in Clément Fondu."** By J. W. Mills. (London: Contractors' Record, Ltd. 1959. Price 16s.)

# Stresses Permissible in Prestressed Concrete.

By P. W. ABELES, D.Sc., M.I.Struct.E.

THE stresses recommended in the new Code<sup>(1)</sup> for the design of members of prestressed concrete are discussed in the following and are compared with the corresponding stresses given in the German Recommendations<sup>(2)</sup> and the U.S.A. Recommendations.<sup>(3)</sup> The new Code replaces an earlier report.<sup>(4)</sup>

## Compressive Stresses Permissible at Transfer.

In the B.S. Code it is recommended that the compressive stress in the concrete at transfer should not exceed 50 per cent. of the crushing strength of work-cubes at twenty-eight days, or 40 per cent. when the prestress is distributed more or less uniformly over the cross-section of the member, and in no case more than 3000 lb. per square inch. However, since creep increases when the ratio of stress to strength exceeds  $\frac{1}{2}$ ,<sup>(5)</sup> and sometimes when it is less,<sup>(6)</sup> it is advisable to restrict the stress to 40 per cent. of the crushing strength irrespective of the distribution of stress as was recommended in an early report<sup>(4)</sup>. The U.S.A. Recommendations give 60 per cent. of the crushing strength of cylinders which is equivalent to about 40 per cent. of the strength of cubes if the strength of a cylinder is two-thirds that of a cube. In the German Recommendations the crushing strength at transfer is assumed to be 80 per cent. of the specified strength of the concrete, of which there are three types, having strengths varying from 4260 lb. to 8520 lb. per square inch. The stresses permissible at transfer are given as a percentage of the strength, namely: for tee-beams, and hollow beams bending in one plane, 42 to 54 per cent.; for rectangular beams bending in one plane, 44 to 58 per cent.; and for members in direct compression 35.5 to 46 per cent. The greater percentage applies to concrete having the lower strength.

## Compressive Stresses Permissible at Working Load.

It is recommended in the Code that the compressive stress in bending due to the working load should not exceed one-third of the crushing strength of cubes at twenty-eight days except at the supports of continuous beams and other statically-indeterminate structures in which a stress of 40 per cent. of the crushing strength is recommended. The compressive stress recommended in direct compression is a quarter of the crushing strength. The permissible stresses due to the greatest working load may be exceeded by up to 25 per cent. if the excess is due solely to the effect of wind.

The corresponding stresses in the U.S.A. Recommendations are 40 per cent. and 45 per cent. of the crushing strengths of cylinders and are equivalent to 27 per cent. and 30 per cent. of the strengths of cubes if the ratio of the strengths of cylinders and cubes is two-thirds. The stresses permitted at working load by the German Recommendations are relatively small and are 1560 lb. to 2270 lb.

- 1.—British Standard Code No. 115 (1959): "The Structural Use of Prestressed Concrete in Buildings".
- 2.—"Tentative Recommendations for Prestressed Concrete." Journal of American Concrete Institute, January, 1958.
- 3.—Spannweiten—Richtlinien für Bemessung und Ausführung." (DIN 4127, 1953).
- 4.—"First Report on Prestressed Concrete." Institution of Structural Engineers (1951).
- 5.—P. W. Abeles. "Notes on Materials for Prestressed Concrete." *Concrete and Constructional Engineering*, September, 1957.
- 6.—P. W. Abeles. "Losses of Prestressing Force." *Concrete and Constructional Engineering*, September, 1958.

TABLE I.—PERMISSIBLE TENSILE STRESSES (B.S. CODE).

STRENGTH (lb per sq.in.)			3000	4500	6000	7500
PRESTRESSED CONCRETE	PRE-TENSIONED STEEL	CASE A			300	325
		CASE B			450	500
	POST-TENSIONED STEEL	CASE A		175	200	225
		CASE B		275	300	325
ADDITIONAL CONCRETE		CASE A	200	250	300	
		CASE B	300	375	450	

per square inch for rectangular beams, 1705 lb. to 2415 lb. per square inch at the corners of rectangular beams subjected to bending in two planes, 1420 lb. to 2130 lb. per square inch for tee-beams, and 1130 lb. to 1850 lb. per square inch for members subjected to direct compression. In each case the lower stress applies to concrete having the lower strength as described for the stresses permitted at transfer.

#### **Tensile Stresses Permissible at Working Load.**

Some designers prefer there to be no tensile stress in the concrete at working load, and this condition is satisfactory if economy is not important, or if it is not essential to reduce the member to the least possible depth. There should be no tensile stress in members, such as turbo-generator bases, which are subjected to a large number of cycles of dynamic load of high frequency. In other cases there is no objection structurally to the existence of tensile stresses within certain limits or to temporary hair-cracks.

The serviceability of a structure at working load may be impaired if cracks are produced. This may happen at a high tensile stress with well-bonded steel in a monolithic member or at a low stress with badly bonded steel. It is possible to prevent cracks when tensile stresses are produced at working load only if it is ensured that no cracks occur before the prestress is applied. In addition to careful design, close supervision of the work and effective curing are essential if freedom from cracks is to be achieved. The permissible tensile stresses in bending as recommended in the Code for members with pre-tensioned and post-tensioned steel are given in *Table I* in which Case A applies when the greatest working load occurs frequently or is of long duration or both, and Case B applies when the greatest working load occurs rarely and is of short duration. The pressure of the wind and the weight of snow on roofs are mentioned in the Code as examples of the latter case. These stresses may be increased by not more than 250 lb. per square inch provided that tests show that the increased stress is not greater than three-quarters of the stress at which the first crack appears as determined by a test. In such a case, therefore, for concrete with a crushing strength of 7500 lb. per square inch at twenty-eight days the greatest tensile stress permissible is 750 lb. per square inch with pre-tensioned steel or 575 lb. per square inch with post-tensioned steel. When the increased stresses are adopted the greatest prestress in the concrete should be at least 1500 lb. per square inch and the pre-tensioned steel should be well distributed; post-tensioned steel (which is usually less well distributed) should, if necessary, be supplemented by non-tensioned steel bars provided near the tensile face of the concrete.

Experience shows that it is possible to avoid cracking even when such high tensile stresses occur. Tensile stresses of 750 lb. per square inch in roofs, and 650 lb. per square inch in road bridges have been adopted with satisfactory results, the adequacy of the design in these cases being controlled by performance tests. When such tests are made, the factor of safety against cracking, despite the higher stresses, is greater than that of a member with post-tensioned steel designed to resist lower tensile stresses but made under poor supervision. If the concrete is inadequately cured, cracks due to shrinking of the concrete may occur before the prestress is applied.

A method of design, particularly suitable for structures with no applied finishes and which is economical and complies with the recommendations of the Code, is one in which there is no limit to the tensile stresses caused in the concrete by occasional heavy loads, provided that no tensile stresses are caused by the normal load. In this case the factor of safety required against failure must be




Fig. 1.

provided for the occasional load, thereby restricting the widths of the cracks. If the occasional load is likely to operate for more than a very short time, it is necessary to investigate the deflection of the member. This method is particularly useful in the design of continuous beams or beams with cantilevered ends in which the load on some spans may cause reversals of bending moments. The envelopes of the diagrams of the greatest possible bending moment and greatest normal bending moment on a beam with a cantilever at one end are shown in Fig. 1a. If the beam is designed to resist the entire range of bending moments with little or no tensile stress in the concrete a very large member is required. If, however, the load causing the greatest possible bending moments is likely to occur rarely, if at all, the method described in the foregoing would lead to a more economical beam. A cantilever will generally be subjected to the full working load and it is therefore necessary to design it to resist the maximum bending moment at the support. The occurrence of the distribution of loading causing the greatest possible bending moments at the supports of a continuous beam (Fig. 1b), however, may be rare and generally the greatest bending moment at a support would be less than the greatest possible bending moment.

In a member which is not exposed to the weather or to a corrosive atmosphere, the permissible tensile stresses in accordance with the U.S.A. Recommendations



are (a) for a member with pre-tensioned steel,  $600 \sqrt{\frac{f'_c}{10,000}}$  lb. per square inch;

(b) for a member with post-tensioned steel,  $300 \sqrt{\frac{f'_c}{10,000}}$  lb. per square inch.

In these expressions  $f'_c$  is the crushing strength of cylinders. For example, if  $f'_c$  is 6000 lb. per square inch, the permissible stresses are 480 lb. and 240 lb. per square inch. These stresses are based on the assumption that the modulus

of rupture has the relatively small value of  $750 \sqrt{\frac{f'_c}{10,000}}$ . The permissible stress

(a) may be exceeded if it is demonstrated by tests that the behaviour of the structure under service conditions is acceptable. It is recommended, however, that there should be no tensile stresses in bridges, or at the joints of members composed of precast elements, but this recommendation is often ignored and, instead, designs of roofs and floors are sometimes based on there being no camber when the dead load only is present; in such cases hair-cracks may develop under the greatest working load. The German Recommendations permit "limited" or "partial" prestressing. The permissible tensile stress varies from 570 lb. per square inch for concrete with a strength of 4260 lb. per square inch to 850 lb. per square inch for concrete with a strength of 8520 lb. per square inch. These values may be increased to 710 lb. and 990 lb. per square inch respectively at the corners of members subjected to bending in two planes.

#### Temporary Tensile Stresses at Transfer and During Transport.

It is recommended in the Code that temporary tensile stresses should not exceed 175 lb. to 225 lb. per square inch for concrete having a crushing strength of 4500 lb. to 7500 lb. per square inch at twenty-eight days. However, greater stresses may be incurred for periods not exceeding forty-eight hours. Tensile stresses in the ends of beams with pre-tensioned steel should preferably be less than the foregoing stresses, as imperfect compaction of the concrete in these regions may give rise to tensile stresses which may exceed the calculated stresses and which may cause undesirable cracking.

When calculating the stresses likely to occur during transport and erection of a member, allowance should be made for the probability of impact; in the writer's opinion, it is desirable to allow an impact factor of  $1\frac{1}{2}$  to 2, and to limit the permissible tensile stress to not more than 500 lb. per square inch.

In the U.S.A. Recommendations the permissible stresses are as follows: monolithic member without non-tensioned steel:  $300 \sqrt{\frac{f'_c}{10,000}}$ ; monolithic member

with non-tensioned steel:  $600 \sqrt{\frac{f'_{et}}{10,000}}$ ; member composed of separate blocks

and with non-tensioned steel:  $300 \sqrt{\frac{f'_{et}}{10,000}}$ , in which  $f'_{et}$  is the crushing strength of cylinders at the age at which transfer takes place. Relating the permissible stress to  $\sqrt{f'_{et}}$  is not entirely satisfactory.

The permissible tensile stresses specified in the German Recommendations



vary from 425 lb. per square inch for concrete with a strength of 4260 lb. per square inch to 640 lb. per square inch for a strength of 8520 lb. per square inch.

### Principal Tensile Stresses.

In some regulations, permissible principal tensile stresses are specified for working-load conditions only. It is, however, essential to provide a specific factor of safety against failure due to shearing as such a failure occurs suddenly with little warning, and the stresses at failure are therefore of much greater importance. It is recommended in the Code that the greatest principal tensile stresses at the load causing failure should not exceed 300 lb., 350 lb., and 400 lb. per square inch in concrete having crushing strengths of respectively 4500 lb., 6000 lb., and 7500 lb. per square inch at twenty-eight days. The corresponding stresses at working load are 125 lb., 150 lb., and 175 lb. per square inch. In all cases, the principal tensile stress should be computed for the effective prestress and the stresses due to the specified loading. When the principal tensile stresses at working load exceed the permissible values, reinforcement to resist shearing should be provided. If the principal tensile stress is more than  $1\frac{1}{2}$  times the tensile stress permissible at working load, the reinforcement should be designed to resist the entire shearing force; for stresses between 1 and  $1\frac{1}{2}$  times the permissible stress the proportion of the shearing force to be resisted by the reinforcement should be interpolated linearly from 0 to 100 per cent. If the principal tensile stress at the load causing failure exceeds the permissible stress, the entire shearing force in excess of that resisted by the inclined prestressing steel should be resisted by reinforcement. It is generally advisable to provide binders unless the calculations show that they are not needed to resist shearing and complete freedom from cracks due to shrinking before the prestress is applied can be assured.

The permissible principal tensile stresses need not be considered to apply at sections where the effects of bending predominate, but only at those sections where shearing is more important, since the suddenness of failure due to shearing makes such a failure potentially more dangerous than the gradual failure due to bending, and while cracks caused by bending due to occasional overloading disappear when the overload is removed, diagonal cracks due to shearing do not close unless inclined cables are provided, and therefore constitute a permanent weakness.

TABLE II.—PRINCIPAL TENSILE STRESSES (GERMAN RECOMMENDATIONS).

LINE	CONDITION	PERMISSIBLE STRESS (lb per sq in)		
		(a) SHEAR ONLY	(b) TORSION ONLY	(c) SHEAR + TORSION
(1)	WHEN DESIGN PERMITS NO TENSILE STRESS DUE TO BENDING AT WORKING LOAD	114 - 172	85 - 142	142 - 213
(2)	WHEN DESIGN PERMITS TENSILE STRESS DUE TO BENDING AT WORKING LOAD	227 - 341	170 - 284	284 - 426
(3)	AT LOAD CAUSING FAILURE	454 - 682	341 - 568	568 - 852

High values correspond to strength of 8520 lb. per square inch

Low	"	"	"	"	"	4260	"	"	"	"
-----	---	---	---	---	---	------	---	---	---	---

Intermediate values obtained by linear interpolation

The stresses which are given in the U.S.A. Recommendations are intended to ensure that failure due to shearing cannot occur before failure in bending, and are based on the yield stress of the steel and the strength of the concrete. The writer considers it doubtful whether the stresses are sufficient for the purpose.

In the German Recommendations permissible principal tensile stresses are specified for shearing only, twisting only, and combined shearing and twisting, and are given in Table II. The smaller stresses are for concrete having a strength of 4260 lb. per square inch and the larger for a strength of 8520 lb. per square inch. No calculations for the shearing reinforcement are required if the permissible stress at the load causing failure is not greater than the stress in line (2) of Table II. Sufficient well-distributed reinforcement must be provided to resist the entire tensile force due to the principal stress wherever the stress exceeds three-quarters of the stress in line (2). If the stress exceeds the appropriate stress in line (3), the cross section must be increased or the stress reduced by increasing the prestressing force. Binders must always be provided in beams, even if the principal stress is less than those given in lines (1) and (2). It is surprising that the principal stresses permitted in partially prestressed members exceed those in fully prestressed members. This requirement is probably based on the assumption that with partial prestressing a smaller factor of safety against cracking may be allowed. This assumption may be true when cracking due to bending is being considered, but it seems better to ensure that a larger factor of safety against cracking due to shearing is obtained in view of the suddenness with which failure due to shearing occurs.

#### **Permissible Stress in Bending in Concrete at Load Causing Failure.**

In the Code it is recommended that, when the steel is initially stressed to between 60 and 70 per cent. of its strength, the mean compressive stress in the concrete at the load causing failure may be assumed to be 40 per cent. of the cube strength, and the depth of the centroid of the stress-block at the load causing failure may be assumed to be 40 per cent. of the depth to the neutral plane. The stress given in the U.S.A. Recommendations is  $0.85 f'_c$ , which corresponds to 56 per cent. of the strength of cubes when the ratio of the strength of a cylinder to the strength of a cube is two-thirds, and 51 per cent. when this ratio is 0.6. The stress specified in the German Recommendations is two-thirds of the strength of cubes; the distribution of stress assumed, however, is such that the results obtained are about the same as those given in the foregoing.

#### **Stress Permissible in Steel at Transfer and Working Load.**

Practice in connection with the permissible stress in the steel at transfer differ considerably. In France, tensioning stresses of up to 90 per cent. of the tensile strength or the yield-point stress are permitted. The German Recommendations specify that the stress must not exceed 55 per cent. of the tensile strength or 75 per cent. of the yield stress or proof stress, whichever is the less. Although 55 per cent. is low, it is preferable to 90 per cent., since at the higher stress a very large part of the elongation of the steel (and consequently its ductility) are no longer available. The initial stress in pre-tensioned steel may be increased to a maximum of 80 per cent. of the yield stress or proof stress, and if friction

occurs the stress at working load in post-tensioned steel may be increased by 5 per cent.

It is recommended in the Code that the initial tensioning stress should not exceed 70 per cent. of the strength of cold-drawn wire. For alloy-steel bars, 70 per cent. of the strength or 85 per cent. of the 0.2-per cent. proof stress (whichever is less) is recommended, the proof stress being based on the smallest cross section of the bar. When alloy-steel bars are used in the pre-tensioned method, the recommended stress is increased to 75 per cent. of the strength or 90 per cent. of the 0.2-per cent. proof stress, whichever is the less.

The maximum tensioning stress given in the U.S.A. Recommendations is 70 per cent. of the strength; a stress of 80 per cent. is permitted for a short period provided that this stress is reduced to 70 per cent. when the tensioning operation is completed. The effective stress in the steel after losses have been deducted should in no case be assumed to exceed 60 per cent. of the strength or 80 per cent. of the yield stress or proof stress.

## Stress due to Bending Permissible in Steel at Load Causing Failure.

The greatest stress in pre-tensioned steel recommended in the Code is equal to the tensile strength, except when the ratio of the tensile strength of the steel to the strength of the concrete multiplied by the percentage of reinforcement is very high. If the depth of the compression zone exceeds 60 per cent. of the effective depth to the steel, the permissible maximum stress is slightly less than the tensile strength. The maximum permissible stress for well-bonded post-tensioned steel is between 75 per cent. and 100 per cent. of the tensile strength, the lower stresses corresponding to higher values of the strength-percentage ratio and to greater depths of the compressive zone. With non-bonded post-tensioned steel it is advisable for the greatest stress to be the same as the initial tensioning stress. The greatest stress in non-tensioned steel should be equal to the yield stress or, in the case of high-strength steel, equal to the 0.2-per cent. proof stress.

In the U.S.A. Recommendations, formulae are given in which a nominal tensile stress is used, which is equal to  $\left(1 - \frac{p \cdot t_u}{2f'_c}\right)t_u$ , in which  $t_u$  is the tensile strength of the steel and  $f'_c$  is the crushing strength of concrete cylinders. For example, if  $t_u = 200,000$  lb. per square inch and  $p = 1$  per cent., the permissible stresses corresponding to  $f'_c = 5000$  lb. and 10,000 lb. per square inch are  $0.8 t_u$  and  $0.9 t_u$  respectively. Only mild steel may be used as non-tensioned reinforcement, and the greatest permissible stress is therefore the yield-point stress.

In the German Recommendations the greatest permissible stress is specified as the yield stress or proof stress for high-tensile steel because definite yielding occurs in most German wire when the proof stress is exceeded. If non-tensioned steel is used, it must be of a type normally used in reinforced concrete; the yield-points or proof stresses for the three types so used are 31,000 lb. per square inch (mild steel), 48,000 lb. per square inch, and 57,000 lb. per square inch.

The use of high-tensile steel for non-tensioned reinforcement is in accordance only with the recommendations of the new Code, and the greatest stress permissible in such reinforcement may be up to 90 per cent. of the tensile strength, if the 0.2-per cent. proof stress is 90 per cent. of the strength.

### Permissible Stresses in Reinforcement Resisting Shearing.

No specific recommendations concerning tensile stresses permissible in shearing reinforcement at working load are given in the Code or the U.S.A. Recommendations, but it is recommended in the Code that the greatest tensile stress be 80 per cent. of the yield-point or the 0.2-per cent. proof stress. This recommendation implies that non-tensioned high-tensile steel may be used as shearing reinforcement.

The German Recommendations specify that the greatest stresses shall be the same as those due to bending, that is, 31,000 lb., 48,000 lb. or 57,000 lb. per square inch.

### Stresses Permissible in Composite Members.

No recommendations or requirements for composite members are given in the U.S.A. Recommendations or the German Recommendations. In the Code it is stated that prestressed beams may be considered to act in conjunction with concrete cast in place if provision is made to resist the horizontal shearing forces at the surface of contact by the use of "shear connectors", or by means of roughening or irregularities of the surface of the concrete. Composite members may therefore be considered to behave as homogeneous members. The Code is the first document to recognise this behaviour, which has been proved by numerous tests, and to recommend tensile stresses in the concrete cast in place. The recommended stresses are only small, but in practice the concrete cast in place is prevented from cracking (except for harmless microscopic cracks) by the restraining effect of the adjacent compressed concrete.

In accordance with the Code, if the greatest working load is of frequent occurrence and of long duration (Case A) the tensile stresses  $f_{3W}$  in the added concrete cast in place (Fig. 2) vary from 200 lb. per square inch, for concrete having a strength of 3000 lb. per square inch, to 300 lb. per square inch when the strength is 6000 lb. per square inch. The corresponding stresses when the maximum load occurs rarely and is of short duration, as in the case of wind and snow on roofs (Case B), are 300 lb. and 450 lb. per square inch. These stresses are given in Table I. The stresses in the concrete cast in place may be increased by 50 per cent. if the stresses  $f_{1w}$  (Fig. 2) are reduced by the same numerical amount. For example, for concrete having a strength of 6000 lb. per square inch, prestressed by means of pre-tensioned steel, and subjected to sustained





Fig. 2.

CUBE STRENGTH 6000 lb. per sq. in.; PRE-TENSIONED STEEL



All stresses are given in lb. per sq. in.

Fig. 3.

maximum loading (Case A), the tensile stresses recommended are 300 lb. per square inch in the prestressed concrete and in the concrete cast in place (Fig. 3a). If the stress in the concrete cast in place is increased by 50 per cent. to 450 lb. per square inch, the stress permissible in the prestressed concrete must be reduced by the same amount, that is to 150 lb. per square inch. If tests show that the increased tensile stress (that is  $300 + 250 = 550$  lb. per square inch) does not exceed 75 per cent. of the stress at which the first crack appears, the stress permissible in the prestressed concrete would then become  $550 - 150 = 400$  lb. per square inch. Stress-diagrams for these conditions are given in Fig. 3a. Similar diagrams for the case of temporary and rare loading (Case B) are given in Fig. 3b.

Many tests have shown that there are no harmful effects if much greater tensile stresses occur in the concrete, and several structures designed on the basis of these higher stresses are now in satisfactory service.<sup>(7)</sup> In Fig. 3c is shown the calculated distribution of stress for a road bridge designed by British Railways (Eastern Region), which has been in use since 1950. The limiting stress for loading of this type (Case A) is given in the Code as 450 lb. per square inch, yet the design stress of 720 lb. per square inch has proved to be satisfactory for this structure.

7.—R. E. Sadler, "Development in Overhead Electrification of Railways as it affects the Civil Engineer." Proc. Inst. Civil Engrs., February, 1959.

### Long Prestressed Lightweight Beams.

Four prestressed beams for the roofs of an auditorium and gymnasium at a school in northern California are each 98 ft. long and of tee-section 5 ft. 3 in. deep. The beams, which were cast at the works of the Basalt Rock Company, Inc., are of lightweight concrete made with expanded-shale aggregate. Each beam, which

contains  $32\frac{1}{2}$  cu. yd. of concrete and weighs 50 tons, is prestressed with nine post-tensioned cables each comprising twelve 0.276-in. wires. The initial compression was 935,000 lb. on each beam and the working force assumed was 774,000 lb. The crushing strength of the concrete is 5000 lb. per square inch.




Fig. 1.—Concreting Plant at Nuclear Power Station: The Gantry Crane. (See page facing.)



## Concreting Plant at a Nuclear Power Station in Scotland.

In Fig. 2 is shown the arrangement of the principal constructional plant at the site of the nuclear power station at Hunterston, Ayrshire. The largest permanent structures are the two reactor buildings (A) and (B) which are 200 ft. high, and the turbine hall (C) which is 672 ft. long, 125 ft. wide, and 58 ft. high and has a basement 11 ft. deep. There are numerous ancillary structures but the general arrangement of the plant is controlled by these large structures and the fabrication on the site of a steel spherical pressure vessel of 70 ft. diameter for each reactor.

fabrication area, and has subsidiary lifting-gears of 30 tons and 5 tons capacity.

Smaller loads, such as skips of concrete, reinforcement, and shuttering, are lifted by 7-ton derrick cranes [(G) in Fig. 2] four of which are provided around each reactor structure (Fig. 1). The cranes have 120-ft. jibs and are on triple steel towers 80 ft. high.

The basement of the turbine hall (Fig. 3) is of reinforced concrete and is served by derrick cranes travelling on rail-tracks, one track being on the floor of the basement and the other on the




Fig. 2.—Arrangement of Plant.

There are also, at each reactor, eight heat-exchangers in the form of steel cylinders 73 ft. 6 in. high and 19 ft. 6 in. diameter and each weighing about 200 tons.

### Cranes.

A 300-tons crane (D), which is installed principally for the erection of the pressure vessels and heat-exchangers, makes it possible to use precast concrete beams weighing up to 300 tons in the upper part of the reactors. The gantry has a span of 208 ft. and the height to the underside of the main girder is about 200 ft.; it can straddle a reactor structure completely (Fig. 1). The crane travels on rail-tracks ((E) and (F) in Fig. 2) from the mechanical engineering workshop and

ground outside the basement walls. A 10-tons jib-crane travelling on two tracks on the floor of the basement is used mainly for the erection of the steel superstructure of the hall. There are also several cranes on road wheels or endless tracks. An electric lift is provided for men working on the reactors.

### Concrete Mixing Plants.

Concrete for the major part of the works is mixed at a main installation and at several secondary plants. Separate mixing plants are provided for outlying works such as the intake and culverts of the cooling-water system. The concrete includes three grades for reinforced concrete, one for prestressed concrete, three



Fig. 3.—Basement of Turbine Hall.

for plain concrete, and one for lean concrete "blinding". A heavy concrete is used for the nuclear-radiation shields.

The main batching and mixing plant shown in *Fig. 4* has a normal capacity of about 40 cu. yd. an hour. There are two batching and mixing installations, one of which comprises two drum-mixers of 1 cu. yd. capacity, and the other one similar mixer. The mixers are within

the steel towers supporting the aggregate-hoppers and batch-weighers. The concrete is discharged from the mixers into tilting or bottom-opening skips, which are transported by lorries and transferred by cranes to the placing position.

The cement is delivered by rail to a station about three miles from the site and conveyed thence by road. (The installation at the station was described




Fig. 4.—The Main Concrete Plant.

in this journal for January, 1959.) The cement is stored in rectangular steel bins, one of 60 tons capacity being provided at each installation, and is conveyed pneumatically, at a pressure not exceeding 15 lb. per square inch, to the batcher. The aggregates are delivered by road and stored in open compartments with concrete floors and dividing walls of timber sleepers. Two compartments are provided for sand and for each size of coarse aggregate, namely,  $\frac{1}{2}$  in.,  $\frac{3}{4}$  in., and  $1\frac{1}{2}$  in.; the total capacity is about 1500 tons. A reserve store with a capacity of about 10,000 tons is also provided. Two electric cranes and one steam locomotive-type grab crane travelling on a steel gantry between the batching plant and aggregates store deliver the aggregates into the hoppers of the batching plant. The coarse aggregate is crushed dolerite; the fine aggregate is sand.

The secondary mixing plant comprises two  $\frac{1}{2}$ -cu. yd. drum-mixers, four steel aggregate bins, and two cylindrical portable cement silos. The aggregate store is arranged radially behind the

mixers and has compartments for sand and  $\frac{1}{2}$ -in.,  $\frac{3}{4}$ -in., and  $1\frac{1}{2}$ -in. crushed dolerite and for various sizes of iron ore (magnetite) for the high-density shielding concrete. The bins are filled by a drag-line bucket operated by a jib-crane on endless tracks. The aggregates are discharged into a batch-weigher which is slung from rails below the bins so that material from any bin can be discharged into any mixer. The concrete is discharged directly from the mixers into skips on lorries on a road under the mixing plant.

During cold weather hot air is blown on to the heaps of aggregates from portable air heaters fitted with flexible trunks. Also, steam is discharged into the middle of the heaps through perforated pipes and hoses connected to the boiler of a steam-crane. The mixing water is heated in two tanks each of 6000 gallons capacity provided with electrical elements in the base. By these means concrete has been mixed and placed when the air temperature has been 22 deg. F. without the temperature of





Fig. 5.—Raft Foundation of Reactor.



**Fig. 6.—Shuttering for Circumferential Beam for Bottom Shield of Reactor.**



**Fig. 7.—Concreting the Bottom Shield of the Reactor.**

the concrete falling below 40 deg. F. A laboratory is provided adjacent to the main mixing plant.

#### Rafts for Reactors.

The ground under the reactor structures, each of which weighs about 77,000 tons, is hard sandstone; the calculated imposed pressure is not more than 10 tons per square foot. The load is distributed by a reinforced concrete raft 7 ft. 6 in. thick, which was constructed in three horizontal layers. Each layer was cast in sections (Fig. 5) at the edges of which precast concrete stop-ends (Fig. 8) were provided. The stop-ends, which are left in position, are grooved across the top and bottom for the passage of the reinforcement bars. The faces are rebated and roughened to ensure a key with the concrete.

#### Bottom Shield of the Reactor.

The superstructure of each reactor structure comprises large reinforced columns supported on the raft and carrying the shield walls, the horizontal shields below and above the pressure vessel, and the building above the reactor for the service machine.

Eight interior columns support a circumferential beam 6 ft. 6 in. deep and stepped to provide a bearing for the bottom shield. The beam was cast in three layers; shuttering was provided for the full depth of the beam including the step (Fig. 6). The bottom shield is circular in plan, 54 ft. 3 in. in diameter and 6 ft. 6 in. thick. It is perforated by 101 openings through which the fuel-elements are passed into the pressure-vessel; the openings are formed by steel sleeves of about 2 ft. diameter embedded in the concrete, and the reinforcement bars in the shield pass between the sleeves.

In each shield there are 397 cu. yd. of concrete, with magnetite aggregate, having a density of not less than 210 lb. per cubic foot when dry; densities of about 220 lb. per cubic foot have been obtained. To avoid joints, which might decrease the efficiency of the shield, this concrete was placed continuously during 39 hours. Before concreting commenced the sleeves were secured to the bottom timber




Fig. 8.—Precast Stop-ends at Construction Joints.

shutter by a cruciform jig and at the top by metal lugs welded to the reinforcement. Two prototypes of a part of the shield had been concreted to determine the best method of placing concrete as quickly as possible in a slab of such depth and complexity, and the method adopted was to mix and place the concrete by the usual means and compact it with immersion vibrators.

The bottom shield was cast after the walls of the reactor structure had been built to about 34 ft. above the shield to give sufficient working space. Fig. 7 shows the work ready for concreting. To avoid interruption in the continuity of casting, reserves of concrete were stored temporarily in four hoppers around the edge of the shield. Normally the concrete was discharged directly into position from each skip; the skips were lowered into the working space by one of the four derrick cranes.




Fig. 9.—Precast Beam Weighing 250 tons.




Fig. 10.—Travelling Shutter for Culvert.






Fig. 11.—Shuttering for the Wall of the Basement of the Turbine Hall.

#### Shield Walls.

The shield walls of the reactors are of reinforced concrete; the inner wall is 5 ft. thick and the outer wall 4 ft. thick. Each wall is divided into eight parts separated by gaps 6 ft. wide. Each part was cast in 5-ft. lifts containing from 80 to 120 cu. yd. of concrete, all of which was placed in one working shift. In order to reduce shrinkage, sections diametrically opposite were concreted successively and the gaps between the sections were filled later.

The shutters for the walls were timber panels 11 ft. long and 5 ft. 6 in. deep made with sheets 6 ft. long and 2 ft. wide of plywood attached to a timber frame similar to those used for the walls of the basement of the turbine hall (Fig. 11) and elsewhere. Immediately after removal of the shuttering the concrete was sprayed with a curing compound; the compound discolours the concrete, but after about four weeks it begins to evaporate and eventually the concrete has its normal colour.

#### Precast Construction.

To enable the construction of the shield walls to proceed without interruption, precast floors are provided where it is convenient to do so. Sections of the floor slabs were cast in the yard between the reactors and lifted into position by the gantry crane.

The top shield over the pressure vessel is 10 ft. 6 in. thick and comprises precast members about 6 ft. 6 in. deep on which concrete is cast to a depth of 4 ft. By means of this construction heavy shuttering, at a great height and in a position where supports would be difficult, is unnecessary. The weight of some of the precast members exceeds 300 tons. Fig. 9 shows a beam of 250 tons ready for lifting by the gantry crane. The lifting tackle comprises wire-rope slings and steel shackles attached to mild steel shafts of 8-in. diameter cast in the beam. Each of the two slings on a beam is attached to one of the twin lifting-hooks of the gantry crane. The ends of these beams are prestressed by B.B.R.V. cables.




Fig. 12.

#### Culverts for Cooling-water.

When it is working at full capacity the station will require about 324,000 gallons of water to be circulated per minute. The water will be taken from the Firth of Clyde about half a mile south of the station and flow through culverts to ducts in the turbine hall. After circulating through the plant the water will proceed through other culverts and be discharged into the Firth to the west of the station. The culverts and ducts are of reinforced concrete. The ducts are of rectangular cross section and were cast in lengths of about 40 ft. Rubber water-stops are provided at each joint. The pipes to and from the condensers were built in during concreting.

The culverts are also of rectangular cross section except for two tunnels, each of 11 ft. diameter and about 550 ft. long, from the intake works off-shore to the pump-house on the shore. The inlet and outlet headworks will be constructed with caissons, which are less liable to damage by heavy seas than are cofferdams. The outlet headworks are about 1100 ft. off-shore. A permanent reinforced concrete jetty about 400 ft. long has been con-

structed to enable road vehicles to reach the intake works.

The shuttering for the rectangular double culverts (Fig. 10) comprises timber panels suspended from a travelling gantry. Four trolleys, to which are attached wire ropes by which the panels are suspended, travel on the bottom flange of the steel cross-head of the gantry and enable the panels to be moved sideways. The cross-head is supported on two steel frames which are carried on bogies running on narrow-gauge tracks on the floor of the culverts. At each position of the gantry the three walls of the culvert can be concreted for a length of 40 ft.

The station is being constructed for the South of Scotland Electricity Board by the General Electric Co., Ltd. Messrs. Simon-Carves, Ltd., are responsible for the design and construction of the civil engineering and building works. The consulting engineers for the cooling-water system are Messrs. L. G. Mouchel & Partners. Messrs. Mowlem (Scotland), Ltd., are the main civil engineering sub-contractors. A photograph taken recently and showing the progress of the work on the reactors is reproduced in Fig. 12.

## Nomograms for the Design of Beams and Slabs by the Load-factor Method.—I.

By J. C. STEEDMAN.

### Rectangular Beams and Solid Slabs: Reinforcement in Tension Only.

THE nomograms on pages 92 to 96 apply to the design of solid slabs and rectangular beams, reinforced to resist tension only, in accordance with the load-factor method as recommended in British Standard Code No. 114 (1957). The accuracy of the results obtained by using the charts is generally sufficient for practical purposes and for checking designs. Separate charts apply to compressive stresses of 1000 lb., 1250 lb., and 1500 lb. per square inch in the concrete with tensile stresses of 20,000 lb. and 30,000 lb. per square inch in the reinforcement. The cross-sectional area of reinforcement required in a beam or slab of any effective depth can be determined for a wide range of applied bending moments. The symbols are as in the Code and the units are in pounds and inches. The bending moments and the area of the reinforcement are expressed in inch-pounds per inch width of beam and per foot width of slab. (Nomograms for a compressive stress of 1500 lb. per square inch will be given in a later number.)

The effective depth required to provide a moment of resistance of  $\frac{p_{cb}}{4} \cdot bd_1^2$  is obtained by direct reading. The effective depth provided should not be less than the depth required; otherwise the nomograms do not apply, as reinforcement in compression is required.

If the stresses in the concrete and reinforcement do not correspond with those in Nomograms Nos. 1 and 2, the percentage of reinforcement required for any ratio of stresses between 10 and 30 can be determined from Nomogram No. 3. The basic formula from which Nomograms Nos. 1 and 2 are derived is

$$M = A_{st} p_{st} l_a, \text{ in which } l_a = d_1 - \frac{3A_{st} p_{st}}{4b p_{cb}}$$

Substituting  $r$  = percentage of reinforcement =  $\frac{100A_{st}}{bd_1}$  and  $R$  = ratio of per-

missible stresses =  $\frac{p_{st}}{p_{cb}}$ :  $\frac{M}{bd_1^2 p_{cb}} = \frac{Rr}{100} \left( 1 - \frac{3Rr}{400} \right)$  and  $l_a = \left( 1 - \frac{3Rr}{400} \right) d_1$ ,


which is the basis of Nomogram No. 3.

The method of using the charts is explained in the examples which follow. The operations required in each example are shown on the relevant nomogram.


EXAMPLE NO. 1.—A solid slab 9 in. thick is subjected to a bending moment of 150,000 in.-lb. per foot of width. Make sure that the thickness is sufficient, and determine the area of reinforcement required if the permissible stresses are  $p_{cb} = 1000$  lb. per square inch and  $p_{st} = 20,000$  lb. per square inch. Since  $d = 9$  in., with  $\frac{3}{4}$ -in. bars and  $\frac{3}{4}$ -in. cover of concrete  $d_1 = 7.87$  in. From Nomogram No. 2A, minimum  $d_1 = 7.07$  in.; therefore the thickness is satisfactory.  $A_{st} = 1.17$  sq. in.; say,  $\frac{3}{4}$ -in. bars at  $4\frac{1}{2}$  in. centres.

(Continued on page 97.)


No. 1A.—DESIGN OF RECTANGULAR BEAMS BY THE LOAD-FACTOR METHOD.  
Reinforcement in Tension Only.



No. 1B.—DESIGN OF RECTANGULAR BEAMS BY THE LOAD-FACTOR METHOD.  
Reinforcement in Tension Only.




NO. 2A.—DESIGN OF SOLID SLABS BY THE LOAD-FACTOR METHOD.  
Reinforcement in Tension Only.






No. 2B.—DESIGN OF SOLID SLABS BY THE LOAD-FACTOR METHOD.

Reinforcement in Tension Only.



No. 3.—DETERMINATION OF CONSTANTS FOR DESIGN OF RECTANGULAR BEAMS AND SOLID SLABS BY THE LOAD-FACTOR METHOD.



(Continued from page 91.)

EXAMPLE NO. 2.—A rectangular beam 9 in. wide is subjected to a bending moment of 1,800,000 in.-lb. Determine (a) the minimum effective depth and area of reinforcement required; (b) the area of reinforcement required if the effective depth is 30 in. Permissible stresses are 1000 lb. per square inch in the concrete and 30,000 lb. per square inch in the reinforcement.

$$M = 1,800,000 \div 9 = 200,000 \text{ in.-lb. per inch of width.}$$

(a) From Nomogram No. 1A, minimum  $d_1 = 28.3$  in.

$$A_{st} = 0.314 \times 9 = 2.83 \text{ sq. in.}$$

(b) Also from Nomogram No. 1A, if  $d_1 = 30$  in.  $A_{st} = 0.281 \times 9 = 2.53$  sq. in.

EXAMPLE NO. 3.—Solve the problem in Example No. 2 if the stresses are  $p_{cb} = 1100$  lb. per square inch and  $p_{st} = 27,000$  lb. per square inch.

$$R = \frac{27,000}{1100} = 24.54.$$

(a) With minimum  $d_1$ ,  $\frac{M}{bd_1^2 p_{cb}} = 0.25$ ; therefore

$$d_1 = \sqrt{\frac{1,800,000}{1100 \times 0.25 \times 9}} = 27.0 \text{ in.}$$

From Nomogram No. 3,  $r = 1.36$  per cent.  $A_{st} = \frac{1.36 \times 9 \times 27}{100} = 3.30 \text{ sq. in.}$

(b) If  $d_1 = 30$  in.,  $\frac{M}{bd_1^2 p_{cb}} = \frac{1,800,000}{30^2 \times 9 \times 1100} = 0.202$ ,

and, from Nomogram No. 3,  $r = 1.01$  per cent.  $A_{st} = \frac{9 \times 30 \times 1.01}{100} = 2.73 \text{ sq. in.}$

Alternatively by calculation, with  $\frac{M}{bd_1^2 p_{cb}} = 0.202$ ,

$$l_a = 0.814 d_1. A_{st} = \frac{1,800,000}{27,000 \times 0.814 \times 30} = 2.73 \text{ sq. in. as before.}$$

(To be concluded.)

### A Viaduct of Ten Spans in North London.

CONSTRUCTION has started of a new viaduct of ten spans to replace the existing Angel Road bridge over the railway at Edmonton, Middlesex. The load on the old bridge, which was the subject of the abstract from this journal of fifty years ago in our number for March, 1959, was restricted to 30 tons, but the new structure has been designed to carry the Ministry of Transport loading. There are to be two carriageways each 30 ft. wide and two footpaths each 10 ft. wide. The total length including the approaches

will be 2550 ft. The viaduct will have five spans of 40 ft. each, four spans of 50 ft., and one span of 57 ft. 6 in. The construction will comprise prestressed concrete beams supported on reinforced concrete piers. A subway for pedestrians will be provided under the eastern approach. The consulting engineer to the Ministry of Transport for this work is Mr. John Mason. The contractors are Messrs. Leonard Fairclough, Ltd. The cost of the bridge and road works will be about £370,000.

## The Late Mr. Arthur W. Legat.

THE death occurred in December last of Mr. Arthur Watson Legat, a former partner in the consulting engineering firm of Messrs. F. A. Macdonald & Partners, Glasgow. Mr. Legat, who was in his sixty-sixth year, was a member of the Institution of Civil Engineers and joint author with Mr. G. Dunn and Mr. W. A. Fairhurst of the book entitled "Design and Construction of Reinforced Concrete Bridges".

MR. W. A. FAIRHURST writes as follows: "Mr. Legat served his apprenticeship with a London firm of civil engineers specialising in harbour works. After service in the First World War he was employed by what is now Truscon, Ltd., and later was in charge of the drawing office of the reinforced concrete department of Sir William Arrol & Co., Ltd., at Glasgow. At the end of 1923 he was appointed chief engineer of the British Reinforced Concrete Engineering Co., Ltd., then at Manchester, and moved with this company to Stafford in 1926, where he remained until the end of 1928. Mr. Legat joined Messrs. F. A. Macdonald & Partners, as a partner, in January 1929, and during the next ten years was engaged in the design and supervision of many types of reinforced concrete and civil engineering works. He was instrumental in securing for the firm the design of many bridges in Scotland, including Inverbervie Bridge (Kincardineshire), Glen Bridge (Dunfermline), a bridge at Guardbridge (Fife), and a bridge over the River Dee at Aboyne (Aberdeenshire). Collaboration with his partner, Mr. George Dunn, resulted in the design and construction of a number of fine bridges. He was a very popular figure in engineering circles throughout Scotland and by numerous lectures and articles did much to advance reinforced concrete construction."

MR. A. P. MASON writes as follows: "Mr. Legat was a man of great ambitions and a first-class engineer who attacked his work with unbounded energy and inspired all those who worked with him. His appointment to the British Reinforced Concrete Engineering Co., Ltd., was like a fresh breeze, and he



devoted himself to laying the foundations of a great design organisation. Although it is a long time since he left the Company, his name remains fresh among the older members of the staff, who held him in the highest esteem."

#### THE UNIVERSITY OF LEEDS BURSARIES IN CONCRETE TECHNOLOGY

Applications are invited for Bursaries in Concrete Technology tenable from 1st October, 1960.

The value of the Bursaries is £400 per annum, out of which the University fees must be paid. The Bursaries will be awarded for one year and may in certain circumstances be renewed for a second year.

Applicants must hold a degree in Engineering, or its equivalent. The course will include post-graduate lectures, design, drawing and laboratory work.

Applications, giving full details of qualifications and experience, together with the names of two referees, must be received by THE REGISTRAR, The University, Leeds, 2, not later than 1st March, 1960.


## A Prismatic-slab Foundation Raft.


THE economy of providing a raft foundation in the form of a number of sloping and horizontal slabs (*Fig. 1*) is described by Mr. I. Martin and Mr. S. Ruiz in the *Journal of the American Concrete Institute* for August 1959. The foundation is for a building in Havana having twenty-four stories and a height above the foundation of 308 ft. The building is designed to resist a wind pressure of 60 lb. per square foot owing to the prevalence of hurricanes. The ground comprises a superficial layer of non-homogeneous marl overlying a mixture of clay and silt on which the raft is founded. The safe bearing pressure is 6000 lb. per square foot. The raft is designed as a prismatic (folded-plate) structure.

The quantities of materials in the raft as constructed and in a raft of conventional planar slab-and-beam construction are as follows.

	As constructed.	Alternative.
Excavation (cu. yd.)	11,510	8764
Concrete (cu. yd.)	2610	4159
Reinforcement (tons)	281	370
Shuttering (sq. yd.)	3754	7436
Earth filling (cu. yd.)	1177	nil

The saving in cost, at prices prevailing in Havana, was 30 per cent., and it is estimated that a saving of about 20 per cent. would be made for a similar foundation at current British prices.







## A Chapel at an Oxford College.

THE Chapel of Westminster College, Oxford, has a precast concrete frame and brick walls, and is above the library which has frames and floors of concrete cast in place. Longitudinal and transverse sections of the structure are given in Fig. 1. The six frames of the chapel (Fig. 4) are parabolic arches, each of which was precast in four parts, namely, the two columns up to the eaves and the

two rafters. The arches are hinged at the floor of the chapel but rigid joints are provided at the eaves and at the ridge.

The columns were erected first (Fig. 2), and bars projecting therefrom are supplemented by reinforcement placed in slots formed in the member (Fig. 3) and concreted to provide a rigid joint. The members are bolted together at the ridge, the bolts passing through holes formed




Fig. 2.




Fig. 3.—Joints at Eaves and Purlins.

## Precast Wall Slabs.

THE illustration shows the erection of precast wall slabs at a two-story building at Mill Hill, London, with a floor area of 25,000 sq. ft. The superstructure was completed in seventeen weeks.

The frames, of which there are 258, are of story height and comprise the mullions between the windows, a lintel, and a wall




Fig. 4.


in the rafters. The bolts are grouted in position. Precast purlins are bolted to the frames at about 6 ft. centres.

At one end of the chapel the shape of the arches at the ridge varies to provide a platform supporting a wooden belfry. At the same end an organ-loft of concrete cast in place is provided. Access to the chapel is by means of two curved stairs (Fig. 4) which are of concrete cast in place. The chapel is one of several new buildings for the college.

The architects are Lord Mottistone and Mr. P. E. Paget and the consulting engineers are Messrs. Hajnal & Myers. The contractors were Messrs. Marshall Andrew & Co., Ltd.

### Tenders for Bridges.

THE Minister of Transport announced recently that a new basis of tendering for large bridges is to be introduced. It is intended that, for schemes in which the requirements might be met equally by two or more types of structure, such as a steel bridge, a suspension bridge, a reinforced concrete bridge, or a prestressed concrete bridge, the tenders submitted may be based on designs prepared by or on behalf of the contractors.



Fixing Slabs in Precast Frames.

slab below each window. The exposed-aggregate slabs are alternately light and dark, the face of those of the lighter colour being smooth and those of the darker colour being rough. The columns are formed by casting concrete in the cavities between the vertical members of adjacent frames.

The system of construction is called "Laingwall" and the building is for the use of the contractors, Messrs. John Laing & Son, Ltd.

## Mesh Reinforcement for Doubly-curved Slabs.

Mr. HERBERT Z. LITTMAN, of Tel-Aviv, has sent us the following description of a welded mesh devised for the reinforcement in three directions of doubly-curved slabs.

It is preferable for the reinforcement bars in a doubly-curved concrete slab, such as a dome, to be in three directions each mutually at an angle of 60 deg., as thereby the tensile forces are transferred directly to the reinforcement and consequently a thinner slab may be used and the risk of cracks is reduced. Attempts to make a welded mesh with three layers of bars each mutually at an angle of 60 deg. have not been successful owing to practical difficulties arising during welding where three bars cross at the same place. If the bars were arranged not to cross in this manner it would be necessary to have a special machine, the bars in the central layer would have to be crimped,

and the resulting mesh would be too rigid to place correctly on a doubly-curved surface.

A satisfactory solution is to provide two sheets of welded mesh each containing bars in two directions at 60 deg. The sheets are laid one above the other. In the bottom sheet the lower bars provide the full cross-sectional area required in one direction, and the upper bars provide half the cross-sectional area required in the central layer in one of the two remaining directions. The top sheet is identical with the bottom sheet but is inverted and placed with the lower bars in the same direction as the upper bars in the bottom sheet, thereby providing the remaining half of the cross-sectional area required in the central layer and the upper bars provide the full cross-sectional area required in the top layer in the third direction.




Fig. 1—Mesh Reinforcement in Position.

The sheets are laid one upon the other in such a way that the bars in the central layer are in the same direction. The sheets are placed so that the overlaps at the boundaries of the top sheet do not coincide with those in the bottom sheet. It is claimed that 1000 square metres (1196 sq. yd.) of two layers of sheets can be laid in six man-days. The illustration (Fig. 1) shows the reinforcement in place.

The sheets are sufficiently elastic to conform to most curved surfaces. The radius of the dome in which the reinforcement was first used is 15 m. (46 ft. 9 in.). The bars in the top and bottom layers are 8 mm. diameter (0.315 in.), and in the central layer 5.7 mm. (0.224 in.). The bars, which were twisted cold, are spaced

at 25 cm. (10 in.) centres. The cost of converting an existing spot-welding machine is comparatively small. Tests\* show that the welds are as sound as welds at the intersection of the wires in ordinary steel fabric and that the welding does not affect the yield stress of the twisted bars.

This reinforcement was developed by Mr. Littman of Reshet Sigma, Ltd., for use in a number of domes in collaboration with the structural engineers, Messrs. Ben-Zvi & Rochman, of Tel-Aviv. It is also used for a dome of 35 m. (115 ft.) radius at the main hall of the Tel-Aviv Jubilee Exhibition, which was constructed by Mr. Vardiman, of Tel-Aviv.

\* See "Welding of Twisted Steel", by H. Z. Littman. Journal of the Association of Engineers and Architects in Israel, September 1958.

### Prestressed Concrete Cylindrical Tanks.

MR. G. D. ALLISON, of Preload, Ltd., writes as follows.

In his paper "How Can the Advantages of Prestressed Concrete best be Utilised?", reported in your number for November 1959, Professor Rusch's observations on wire-wound cylindrical tanks convey an impression of a risk of corrosion which in fact need not exist. Professor Rusch does not mention the very important point that the protective cover of gunite should be allowed to harden while the tank is full, as stated in the article on page 12 of your number for January 1960, so that no tensile stress will develop in the gunite. Also, continuing creep of the prestressed concrete wall actually induces a small compressive stress, and the gunite effectively bonds and protects the wire.

### Association for Shell Structures.

AN International Association for Shell Structures (IASS) was formed recently to aid the development of structural shell construction by means of meetings to facilitate interchange of ideas, and the publication of articles in technical journals. The Association intends to hold a colloquium on precast shells in the autumn of 1960 (at Warsaw or Dresden). Particulars of the Association are obtainable from the Secretariat of the International Association for Shell Structures, Alfonso XII, 3; Madrid (7), Spain.

### Training Courses on Concrete.

THE number of training courses on concrete held at the research station of the Cement and Concrete Association at Wexham Springs, Bucks., is to be doubled in 1960 and include some sessions which previously had been held at intervals of two or three years. In addition to the usual courses there will be two sessions for architects, courses for farmers, estate managers and the like, on farm buildings, and two courses for builders. Two courses for engineers will deal with the design of prestressed and reinforced concrete bridges.

The provisional programme includes the following: February 15 to 19 and February 22 to 26, Design of prestressed and reinforced concrete bridges (for engineers). February 29 to March 4 and March 7 to 11, Concrete construction (for builders). March 14 to 18, Concrete construction for farms. March 21 to 25 and March 28 to April 1, Concrete and soil-cement roads (for supervisors). June 13 to 17, June 20 to 24, September 19 to 23, and September 26 to 30, Structural concrete (for engineers). June 27 to July 1, Soil-cement roads and airfields (for engineers). July 4 to 8, Concrete roads and airfields (for engineers). July 11 to 15 and July 18 to 22, Concrete for architects. From October 3 to December 9 there are nine courses on structural concrete (for supervisors).

Full details of the courses can be obtained from the Association, 52 Grosvenor Gardens, London, S.W.1.

**A TRICOSAL TIME-TESTED JOB****London Bridge Station  
Bus Terminus****OTHER OSAL PRODUCTS**

**Florosal for Surface Hardening and  
Protection of Concrete, Stone  
and Cement.**

*Send for Information Leaflet No. 2*

**Neocosal for Surface Waterproofing  
of Brick, Concrete and Stone.**

*Send for Information Leaflet No. 3*

**A. A. BYRD & CO. LTD., Dept. C., 210 Terminal  
House, Grosvenor Gardens, London, S.W.1.**

Phone: SL 0200 8336

Grams: Byrdicom, Wasphone, London

Works: Basingstoke, Hants.

To provide a hard-wearing and  
oil-resisting surface Tricosal,<sup>1</sup>  
diluted with sixteen parts water,  
was incorporated in the 6" thick  
4:2:1 concrete Bus Station  
surface. Finished in May 1957,  
the surface today shows no signs  
of wear.



**An Osal Product**

**INDISPENSABLE FOR CEMENT WORK**

*Send for Information Leaflet No. 1*

The sheets are laid one upon the other in such a way that the bars in the central layer are in the same direction. The sheets are placed so that the overlaps at the boundaries of the top sheet do not coincide with those in the bottom sheet. It is claimed that 1000 square metres (1196 sq. yd.) of two layers of sheets can be laid in six man-days. The illustration (Fig. 1) shows the reinforcement in place.

The sheets are sufficiently elastic to conform to most curved surfaces. The radius of the dome in which the reinforcement was first used is 15 m. (46 ft. 9 in.). The bars in the top and bottom layers are 8 mm. diameter (0.315 in.), and in the central layer 5.7 mm. (0.224 in.). The bars, which were twisted cold, are spaced

at 25 cm. (10 in.) centres. The cost of converting an existing spot-welding machine is comparatively small. Tests\* show that the welds are as sound as welds at the intersection of the wires in ordinary steel fabric and that the welding does not affect the yield stress of the twisted bars.

This reinforcement was developed by Mr. Littman of Reshet Sigma, Ltd., for use in a number of domes in collaboration with the structural engineers, Messrs. Ben-Zvi & Rochman, of Tel-Aviv. It is also used for a dome of 35 m. (115 ft.) radius at the main hall of the Tel-Aviv Jubilee Exhibition, which was constructed by Mr. Vardiman, of Tel-Aviv.

\* See "Welding of Twisted Steel", by H. Z. Littman. Journal of the Association of Engineers and Architects in Israel, September 1958.

### Prestressed Concrete Cylindrical Tanks.

Mr. G. D. ALLISON, of Preload, Ltd., writes as follows.

In his paper "How Can the Advantages of Prestressed Concrete best be Utilised?", reported in your number for November 1959, Professor Rusch's observations on wire-wound cylindrical tanks convey an impression of a risk of corrosion which in fact need not exist. Professor Rusch does not mention the very important point that the protective cover of gunite should be allowed to harden while the tank is full, as stated in the article on page 12 of your number for January 1960, so that no tensile stress will develop in the gunite. Also, continuing creep of the prestressed concrete wall actually induces a small compressive stress, and the gunite effectively bonds and protects the wire.

### Association for Shell Structures.

AN International Association for Shell Structures (IASS) was formed recently to aid the development of structural shell construction by means of meetings to facilitate interchange of ideas, and the publication of articles in technical journals. The Association intends to hold a colloquium on precast shells in the autumn of 1960 (at Warsaw or Dresden). Particulars of the Association are obtainable from the Secretariat of the International Association for Shell Structures, Alfonso XII, 3; Madrid (7), Spain.

### Training Courses on Concrete.

THE number of training courses on concrete held at the research station of the Cement and Concrete Association at Wexham Springs, Bucks., is to be doubled in 1960 and include some sessions which previously had been held at intervals of two or three years. In addition to the usual courses there will be two sessions for architects, courses for farmers, estate managers and the like, on farm buildings, and two courses for builders. Two courses for engineers will deal with the design of prestressed and reinforced concrete bridges.

The provisional programme includes the following: February 15 to 19 and February 22 to 26, Design of prestressed and reinforced concrete bridges (for engineers). February 29 to March 4 and March 7 to 11, Concrete construction (for builders). March 14 to 18, Concrete construction for farms. March 21 to 25 and March 28 to April 1, Concrete and soil-cement roads (for supervisors). June 13 to 17, June 20 to 24, September 19 to 23, and September 26 to 30, Structural concrete (for engineers). June 27 to July 1, Soil-cement roads and airfields (for engineers). July 4 to 8, Concrete roads and airfields (for engineers). July 11 to 15 and July 18 to 22, Concrete for architects. From October 3 to December 9 there are nine courses on structural concrete (for supervisors).

Full details of the courses can be obtained from the Association, 52 Grosvenor Gardens, London, S.W.1.



**A TRICOSAL TIME-TESTED JOB****London Bridge Station  
Bus Terminus****OTHER OSAL PRODUCTS**

**Florosol for Surface Hardening and  
Protection of Concrete, Stone  
and Cement.**

*Send for Information Leaflet No. 2*

**Neocosol for Surface Waterproofing  
of Brick, Concrete and Stone.**

*Send for Information Leaflet No. 3*

To provide a hard-wearing and oil-resisting surface Tricosal,<sup>1</sup> diluted with sixteen parts water, was incorporated in the 6" thick 4:2:1 concrete Bus Station surface. Finished in May 1957, the surface today shows no signs of wear.



**A. A. BYRD & CO. LTD., Dept. C, 210 Terminal  
House, Grosvenor Gardens, London, S.W.1.**

Phone: SLOane 5236      Grams: Byrdison, Westphone, London  
Works: Basingstoke, Hants.

**An Osal Product**

**INDISPENSABLE FOR CEMENT WORK**

*Send for Information Leaflet No. 1*

# **STELMO**

## **LIMITED**

### **announce their**

### **NEW ADDRESS**

**WESTWELL LEACON,  
CHARING, ASHFORD,  
KENT.**

**TELEPHONE: CHARING 395-7**


This new and up-to-date works, with its greater design-department facilities, will enable us to meet the ever-increasing demand for the specialised STELMO products and services so well known throughout the world.

## Deep Cylindrical Foundation Piers.

CYLINDRICAL foundation piers to carry loads up to 2000 tons at depths up to 80 ft. are being constructed for buildings in London and elsewhere by means of the plant shown in the illustrations. The procedure is to bore a hole to the required depth by means of an auger and to fill the hole with concrete. The auger (*Fig. 1*) is from 3 ft. to 7 ft. in diameter and is attached to the end of a vertical hollow square steel shaft which is suspended from the crane jib of an ordinary heavy excavating machine. A cantilevered member carrying the guide and rotating mechanism for the shaft is fixed to the excavator, the motor or engine and winches of which provide the power and motions for the shaft and auger. The advantages of using an excavator are that the boring device is mobile, that a standard machine can be adapted, and that when it is not used for boring it can be readily converted for use as a crane or excavator.

The auger is worked into the ground by screw-action aided by the weight of the shaft. In very hard ground the sinking can be assisted by an hydraulic jacking device attached to the guide. The length of the shaft, within which is another shaft, is about 50 ft. When the hole has been bored to this depth the inner shaft comes into operation automatically and boring proceeds to the depth required. The helical blade of the auger comprises about two complete turns. The auger rotates clockwise when boring and after each downward travel equal to about the length of the auger the rotation is stopped and the auger is brought to the surface (*Fig. 1*), the jib is swung round and, by an anti-clockwise rotation of the shaft and auger, the excavated soil on the screw is flung off. The jib is then swung back and the auger is lowered into the bore to make a further cut.

If the area at the base of the pier is required to be greater than that of the hole excavated by the auger, a device (*Fig. 2*) comprising cutters projecting from a steel cylinder is lowered to the bottom of the bore and rotated. The link-motion to which the cutters are attached causes them to extend progressively farther out of the cylinder as the



**Fig. 1.**

side of the bore is excavated so that an enlarged cavity is formed in the ground. The diameter of the cavity is about twice that of the auger, and the diameter of the largest cavity which can be formed is about 15 ft.

The bore, and the cavity (if any) at the base, are filled either by dropping concrete through a sheet-metal funnel at the top of the bore or by lowering it in bottom-opening skips. It is claimed that a well-consolidated concrete is produced by the former method due to the impact of the falling material, which has a slump not exceeding 3 in. Immersion vibrators are used to compact the concrete in the upper part of the pier.

The method is most suitable for piers in clay, in which case boring may proceed at a rate exceeding 20 ft. per hour. If the top strata are loose a steel lining is sunk as boring proceeds and is withdrawn as the concrete is placed. The load-carrying capacity of the piers depends on bearing at the bottom and friction on the sides. Most of the piers so far driven are in firm clay for a considerable proportion of their depth; this has the advantages of increasing the area subjected to frictional resistance and of




Fig. 2.





Fig. 3.—Loading Test on Piles.

## Multi-wire strand For prestressed concrete



This photograph shows the stressing of multi-wire "Bridge" Strand at the Perth Narrows Bridge in Australia. "Bridge" Strand is made from Somerset Wire.

CONSULTING ENGINEERS: G. Maunsell & Partners  
PRESTRESSED CONCRETE CONSULTANT: E. W. H. Gifford  
CONTRACTORS: Christiani & Nielsen Ltd.

**IF YOU WANT TO PUT STEEL INTO CONCRETE  
GET IN TOUCH WITH**

**GKN Reinforcements Ltd**

197 KNIGHTSBRIDGE, LONDON, S.W.7. KENsington 6311

SMETHWICK, BIRMINGHAM (Smethwick 1991) • MANCHESTER (Ardwick 1691)  
GLASGOW (Bell 2444) • MIDDLESBROUGH (3943) • CARDIFF (Cardiff 45220)  
BRISTOL (Bristol 21555) • LEICESTER (Leicester 25114) • LEEDS (Leeds 27311)

WORKS AT CARDIFF, SMETHWICK, WIGAN & GLASGOW

# Pipe- jointing

**STRONG WATERTIGHT JOINTS**

**IN THE MINIMUM OF TIME \***

\*  
within a few hours drains can be smoke-tested  
or water-tested and trenches filled in

no other type of cement gives such  
**SOUND AND SPEEDY RESULTS**



*The Cement for Industry*

**LAFARGE ALUMINOUS CEMENT CO. LTD.**

73 BROOK STREET, LONDON, W.1. TEL: MAYfair 8546



bearing on confined clay which is likely to have a greater resistance than clay nearer the surface.

This method of constructing cylindrical piers was developed in Great Britain by Economic Foundations, Ltd., and among the foundations constructed by this means are about 150 piers of 4 ft. 6 in. and 7 ft. diameter 70 ft. deep, with enlarged bases, for the new building at South Bank, London, for the Shell Petroleum Co., Ltd. About three hundred foundations of this type are also provided for some of the structures adjacent to the reactors at the nuclear power station at Bradwell, Essex. These piers, the greatest load on which is 350 tons, penetrate 35 ft. of filling and brown clay and extend about 10 ft. into the underlying hard blue clay.

### Tests.

Four piles of this type each of 3 ft. diameter were recently tested with loads up to 1000 tons. One pair extended to a depth of 55 ft. to clay having a shearing

strength of  $2\frac{1}{2}$  tons per square foot, and the other pair extended to a depth of 40 ft. where the clay had a strength of  $1\frac{1}{2}$  tons per square foot. One pile in each pair was the same diameter throughout, but on the other an expanded foot of 7 ft. diameter was formed. Each of the plain piles contained near the bottom a compressible layer which would transfer appreciable load to the bottom of the pile only after the frictional resistance on the sides had broken down; by this means the frictional resistance and the bearing resistance could be determined separately. The testing rig is shown in Fig. 3. The load was imposed by hydraulic jacks coupled together. The forces imposed by the jacks were measured by four 250-tons electrically-balanced pressure cells, which were made specially for this test. The results of the tests confirmed that the calculated loads were safe. The tests were carried out under the supervision of Messrs. R. H. Harry Stanger.

### Lectures on Building.

THE following lectures have been arranged by the Ministry of Works. Admission is free.

Building High, by N. Wakefield at the Technical College, Cambridge; February 15, 7.30 p.m.

Thermal Insulation of Buildings, by N. Foster at the Grosvenor Museum, Chester; February 15, 7.15 p.m.; and by R. R. Houston at the College of Technology, Portsmouth; February 25, 7.15 p.m.

The Builder and his Contract, by R. Proctor at the Technical College, York; February 16, 7.15 p.m.

Introduction to Programming and Progressing for Builders, by A. E. Chittenden at the Grand Hotel, Cardiff; February 17, 7.15 p.m.

Four New Techniques in Building, by D. Bishop at Willesden Technical College, London, N.W.10; February 17, 7.15 p.m.

Safety in the Building Industry, by J. A. Hayward at Hertfordshire College of Building, St. Albans; February 18, 7.15 p.m.

Dampness in Buildings, by W. A. Hammond at the Technical College, Carlisle; February 22, 7 p.m.

Settlement of Buildings, by S. R. Rosenak at S.E. London Technical College, London, S.E.26; February 22, 7.15 p.m.

February, 1960.

Work Study in Building, by R. Geary at the Town Hall, Lancaster; February 24, 7.30 p.m.

R.I.B.A. Form of Contract, by I. N. D. Wallace at the City College, Norwich; February 24, 7.15 p.m.

Concrete Placing and Formwork, by A. B. Harman at the Technical College, Newport, Isle of Wight; February 24, 7 p.m.

Clerical Methods in Builders' Offices, by K. C. Symons at the Technical College, Neath; February 25, 7 p.m.

Practical Formwork, Design, and Construction for Concrete, by J. G. Richardson at the Medway College of Technology, Chatham; February 26, 7.15 p.m.

### THE UNIVERSITY OF LEEDS

The University offers a one-year full-time course for a Diploma in Concrete Technology commencing in October, 1960. The course consists of lectures, laboratory work and a design or research project.


Applications for admission to the course are invited from graduates and from holders of equivalent qualifications in engineering. Preference will be given to applicants who have had one or two years' practical experience.

Further information may be obtained from the REGISTRAR, The University, Leeds, 2.

## FIFTY YEARS AGO.

From "CONCRETE AND CONSTRUCTIONAL ENGINEERING", February, 1910.

## Reinforced Concrete Chimneys at Northfleet.



THE illustration shows some chimneys at the cement works of the Associated Portland Cement Manufacturers, Ltd., at Northfleet, Kent. Two of the chimneys are of reinforced concrete and had been recently completed in 1910. "The taller chimney is 247 ft. in height above bottom of foundations; the thickness of the shell up to 62 ft. above the ground-level was as follows: outer shell, 12 in.; cavity, 4 in.; inner shell, 4 in. Above this the chimney consisted of a single shell 9 in. in thickness. The reinforcement in the shell consisted of rings of steel  $\frac{1}{2}$  in. diameter, spaced 18 in. apart, and vertical bars formed of  $1\frac{1}{4}$ -in.  $\times$   $1\frac{1}{4}$ -in.  $\times$   $\frac{3}{16}$ -in. T's." The smaller chimney is 130 ft. high, the shaft being reinforced similarly.

## Tests of Water for Concrete.

MR. K. H. BRITAIN writes as follows regarding the review of B.S. No. 3148 in our number for December, 1959.

"Many engineers will prefer the method, which their grandfathers established, of testing the suitability of water in a way which they themselves understand with equipment available in concrete laboratories. The alternative of specifying the water on the lines of the French and U.S.A. recommendations

(which were duly considered by the Committee) involves the use of a chemical analytical laboratory to produce figures which have no obvious meaning for most engineers. The language in the British Standard is simple and sensible; the cost is high, but surely this is inevitable if a complete Government subsidy is to be avoided. I hope your paragraph on this Standard will not stop engineers reading it and using it."

## MISCELLANEOUS ADVERTISEMENTS.

**Situations Wanted, 5d. a word: minimum, 12s. Situations Vacant, 6d. a word: minimum, 15s. Other miscellaneous advertisements, 6d. a word: minimum, 15s. Displayed advertisements, 40s. per column inch. Box number 1s. extra.**

**Advertisements must reach this office, 14 Dartmouth Street, London, S.W.1, by the 23rd of the month preceding publication.**

## SITUATIONS VACANT.

**SITUATIONS VACANT.** Consulting engineers have vacancies for reinforced concrete detailers, and designer-detailers. Salaries in accordance with experience. Luncheon vouchers. Apply in writing to BYLANDER, WADDELL & PARTNERS, 169 Wembley Park Drive, Wembley, Middlesex.

**SITUATIONS VACANT.** E. J. COOK & Co. (ENGINEERS) LTD. require five reinforced concrete designer-detailers for expanding design office. Not less than ten years' experience, H.N.C. or similar level. Salaries £800-£1200 per annum according to experience and ability. Five-days' week. Luncheon vouchers. Superannuation scheme after twelve months' service. Application forms from 34 South Side, Clapham Common, London, S.W.4 (Macaulay 5522).

**SITUATIONS VACANT.** Small structural engineering office, London, W.C.1 area, with extensive practice, requires additional assistants. Capable men from graduate-ship upwards required for high-class miscellaneous work generally, foundations, dangerous structures, steel, concrete and timber, and able to work with minimum supervision. Reply in confidence, with full particulars, and salary required, to BOX 4634, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATIONS VACANT.** Detailer and designer-draftsmen required for rapidly expanding reinforced concrete design office. Permanent superannuated positions. Five-days' week. Excellent working conditions in modern offices with canteen. Write, stating experience, age, and salary required, to THE SECRETARY, THE ROM RIVER CO. LTD., 100 Stewart Road, Battersea, London, S.W.8.

**SITUATIONS VACANT.** Assistant engineers, steelwork designer-draftsmen, reinforced concrete designer-detailers, and detailer-draftsmen required for varied and interesting work on structures for industrial, commercial, medical, and residential buildings. Five-days' week. Luncheon vouchers. Apply, with details of experience, and salary required, to JOHN F. FARQUHARSON & PARTNERS, Chartered Structural Engineers, 34 Queen Anne Street, London, W.1. Telephone Langham 6011.

**SITUATIONS VACANT.** Reinforced concrete designers and detailers required. Minimum three years' practical experience on structural work. Good salary and prospects for right men. Written applications to JOHN LIVERIDGE & ASSOCIATES, 43 Portland Place, London, W.1.

## STRUCTURAL ENGINEERS

**ENGINEERS** required in Architect's Department, London County Council. Up to £1,135 (under review) and with good prospects.

(A) *Structural Engineering Division.*—Extensive programme includes multi-storey flats, schools, offices, warehouses and other buildings.

(B) *Structural Engineering Division.*—To deal with applications in respect of special structures under Part IV of London Building Act (A), 1939, and the constructional by-laws. Interesting work involving consideration of unconventional forms of construction.

(C) *District Surveyors' Service.*—Work mainly outside involving negotiations with architects, engineers and surveyors and supervision of works in progress.

Application form and particulars from HUBERT BENNETT, F.R.I.B.A., Architect of the Council, EK/112/59, County Hall, London, S.E.1. (2629.)

# Truscon

## in 1960

Truscon drawing offices are now busier than ever, and interesting, challenging schemes of great variety are arriving at our office every day. This means that our reinforced concrete design staff, which over the years has been steadily growing, now needs the support of extra men, and, essentially, men of the right character and quality.

We hope that these men will help to maintain Truscon's own tradition of quality—and this applies both to construction and design. Indeed it may be that the early collaboration between our design and construction staff, together with the constant interchange of information between office and site which an organisation such as Truscon permits, will of itself prove an attraction to the ambitious and imaginative, yet experienced, men we are seeking for our design offices.

The following positions are vacant:

## London

Two reinforced concrete design engineers, with first-class experience of both project schemes and working drawings. Two reinforced concrete detailers, again with first-class experience.

## Harlow, Birmingham and Manchester

In each office: one designer and one detailer with similar qualifications to the above.

Please write initially to our Director—Engineering at Truscon House, Lower Marsh, London, S.E.1, giving brief details of your qualifications, positions held, experience gained and salaries earned. We are anxious to give applicants every opportunity to justify themselves at an interview, which will be in confidence and can, if necessary, be arranged outside business hours.

Jobs with Truscon are, subject to usual conditions of employment, permanent and secure yet progressive. Salaries are good, as are holidays and sick pay entitlement. We have a good pension scheme, with dependents' benefits, and a profit-sharing scheme for staff. Promotion is by merit alone, and although we already have a number of mature young men holding down responsible posts, there's always room for more. We shall be pleased to hear from anyone who would like to discuss the possibilities of joining Truscon in 1960.

**SITUATIONS VACANT.** South London consulting engineers require experienced reinforced concrete engineers, designer-draftsmen, and detailers. Applicants should have a minimum experience of three years in position applied for. Salary commensurate with experience and ability. Luncheon vouchers, and five-days' week. Please write, giving details of age, qualifications, and experience, to LEONARD & GRANT, 344 South Lambeth Road, London, S.W.8.

**SITUATION VACANT.** Manager required for rapidly-expanding sectional concrete building works. Must have good organising ability and be strong disciplinarian. Duties are to supervise and control all departments of this company, which include model, carpentry, steel fabrication, despatch, and erection departments. This is a permanent position, and offers good prospects to suitable applicant. Please write in complete confidence, giving details of experience, and present salary, to MANAGING DIRECTOR, W. TIBBETS & SONS LTD., Barford Road, Bloxham, Oxon.

**SITUATIONS VACANT.** Structural and civil engineers require senior and intermediate designer-detailers experienced in either (1) reinforced concrete, or (2) structural steelwork. Excellent opportunities in an expanding organisation for the right men. Positions are pensionable, and offer first-class experience. Box 4639, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATION VACANT.** Keen, conscientious young production engineer experienced in concrete techniques, required for position in expanding precast, cast stone and reinforced concrete industry in Southern county. Ability to organise and assist in supervision of work in maintaining high standard of products. Excellent prospects. Write, stating age, experience, present situation, any qualifications, and salary required. Replies, treated in strict confidence, to Box 4641, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**SITUATIONS VACANT.** Reinforced concrete specialist firm requires designer-detailers. Interesting and varied work. Some previous experience. Write CHIEF ENGINEER, CANTON REINFORCED CONCRETE LTD., 45 Bedford Road, London, W.C.1.

**SITUATIONS VACANT.** Civil Engineering Assistants required for site work on contracts. The work is varied and interesting with opportunities for promotion and study of new methods. Applicants should be between the ages of 26 and 32, and hold a degree in civil engineering or equivalent. They should have had a minimum of 3 years with a contractor on site work, which must have included setting-out and progress measurement. Experience in design of formwork and other temporary works, control of concrete quality would be an advantage. Apply in writing, giving brief details of qualifications and experience, also stating age, and salary required, to THE CHIEF ENGINEER, THE DEMOLITION & CONSTRUCTION CO. LTD., 3 St. James's Square, London, S.W.1.

**SITUATIONS VACANT.** Junior Civil Engineers required to work on sites with excellent opportunities for training. Applicants should be graduates or equivalent and should be between the ages of 20 and 26. Apply in writing, giving brief details of qualifications and experience (including vacation course work), also stating age, to THE CHIEF ENGINEER, THE DEMOLITION & CONSTRUCTION CO. LTD., 3 St. James's Square, London, S.W.1.

**SITUATION VACANT.** W. & C. FRENCH LTD. urgently require designer/detailer mainly for reinforced concrete design and detailing. Applicants must be keen to learn about new methods and types of construction. Apply in writing, stating age, salary required and full details of experience, to PERSONNEL MANAGER, 50 Epping New Road, Buckhurst Hill, Essex.

**SITUATION VACANT.** Experimental or assistant experimental officer required for building materials research laboratory. Applicants should have a degree in physics, engineering, or building technology, or Higher National Certificate or equivalent, and preferably some experience of mechanical testing work. The appointment will be made at an initial salary appropriate to qualification. Apply, DIRECTOR OF RESEARCH, THE CHALK LIME AND ALLIED INDUSTRIES RESEARCH ASSOCIATION, Church Street, Welwyn, Herts.

**SITUATIONS VACANT.** Reinforced concrete detailers and designers required in North West London. Three-weeks' paid holiday, and excellent prospects in small expanding firm. Telephone Maidstone 7890.

**SITUATIONS VACANT.** Air Ministry Works Design Branch requires in London structural engineering designer-draftsmen for reinforced concrete or structural steelwork of all types. Applicants must have adequate training and several years' experience. Some site experience and possession of recognised technical qualification an advantage. Financial assistance and time off may be allowed for recognised courses of study. Promotion and pension prospects. Five-days' week with 18 working days leave per year initially. Salary for Grade III ranges from £680 (at age 25) to £900 per annum. Commencing salary dependent on age, qualifications and experience. Also vacancies in higher grade for suitably qualified candidates on range from £895 to £1,055 per annum. Applicants, who must be natural born British subjects, should write to Air Ministry, W.G.C., Lacon House, Theobalds Road, London, W.C.1, or to any Employment Exchange (quoting Order No. Kings Cross 3745) giving age, details of training, qualifications, full particulars of former posts held and copies of any testimonials. Candidates selected will normally be interviewed in London and certain expenses reimbursed.

### THREE REPRESENTATIVES REQUIRED

Opportunities for three enthusiastic young men to obtain positions on Sales Technical Staff of Company with renowned products indispensable to reinforced concrete construction. Initially mobile over 50-mile radius of following approximate locations:

1. South Coast-London.
2. Tipton-Wolverhampton.
3. Leeds.

Knowledge of reinforced concrete, and driving licence advantageous.

Applicants must be of pleasant personality, keen, energetic, conscientious, adaptable, and should have been educated to the standard of G.C.E.

Written applications, treated in strict confidence, with full particulars, details of qualifications, etc., to Box 4640, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

### GENERAL MANAGER

Thoroughly experienced and capable general manager required to take complete charge of wire straightening, cutting and bending works. Duties will include sales and purchase of raw material. Lucrative position and bonus scheme, with excellent possibilities of advancement. Apply in strict confidence, detailing experience, to Box 4642, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

### BRITISH RAILWAYS WESTERN REGION

Applications are invited for Structural Draughtsman experienced in preparing estimates and contracts for the supply and erection of steel and concrete bridges, etc. Drawing office and costing experience essential. Salary range £831/903.

Travel concessions, holidays with pay, with prospects of promotion and permanency, and membership of Superannuation Fund.

Applications stating age, previous experience, etc., to Chief Civil Engineer, B.R. Western Region, Paddington Station, London, W.2.

**SITUATION VACANT.** W. & C. FRENCH LTD. urgently require architectural draughtsman and practical building detailer for interesting work of considerable variety. Apply in writing, stating age, salary required and full details of experience, to PERSONNEL MANAGER, 50 Epping New Road, Buckhurst Hill, Essex.

**SITUATIONS VACANT.** Consulting engineers urgently require additional staff in London and Dartington. Engineers and draughtsmen for both reinforced concrete and steelwork. Full particulars to F. R. BULLEN & PARTNERS, Drake House, Dean Farrar Street, London, S.W.1.

**SITUATIONS VACANT.** Civil and structural. Graduate engineers and designer-draughtsmen required for all types of design work on large civil and structural engineering projects in the U.K. and overseas. Resident engineer positions also available. A high rate of earnings is paid in this firm to those with initiative and ability. London Office of R. T. JAMES & PARTNERS, Consulting Civil Engineers, 6 Lower Grosvenor Place, London, S.W.1.

**SITUATION VACANT.** Experienced structural draughtsman required. Generous salary offered for first-class man capable of fast, accurate detailing and with the ability to work without close supervision. Please apply to R. L. BOURQUE & PARTNERS, Thernia House, Kingston-upon-Thames, for an appointment. (Elinbridge 0430 or 0888).

**SITUATION VACANT.** Reinforced concrete specialist firm requires designer/detailer. Interesting and varied work. Luncheon vouchers, pension scheme, etc. Only experienced men need apply. Write the REINFORCED CONCRETE STEEL CO. LTD., 54 Victoria Street, Westminster, S.W.1.

**SITUATION VACANT.** Civil engineering assistant required for design and drawing of reinforced concrete industrial structures and foundations. Apply to the Chief Engineer, THE A.P.C.M. LTD., Portland House, Tothill Street, London, S.W.1.

**SITUATION VACANT.** Draughtsman-estimator for interesting work in connection with roof and floor beams. Opportunity to progress with a rapidly-expanding company. Pension scheme, and canteen facilities. Apply, giving full details of age, experience, and present position, to the Office Manager, MARLEY CONCRETE LTD., Peasmarsh, near Guildford, Surrey.

**SITUATION VACANT.** Senior engineer required for London professional office. Must have professional qualifications, preferably degree, and at least five years' design experience in structural reinforced concrete. Knowledge of steelwork an advantage. Age limit 30-40. Candidates should have site experience, and be capable of handling contracts from start to finish. The work is varied and offers scope for initiative. A good salary will be offered. Apply, stating experience, and salary required, to FARMER & DARK, Romney House, Tufton Street, Westminster, S.W.1.

**SITUATIONS VACANT.** Reinforced concrete detailers for London professional office. Experience of steelwork an advantage but not essential. The work is varied and offers scope for initiative. Five-days' week. Please apply, giving full details, and salary required, to FARMER & DARK, Romney House, Tufton Street, Westminster, S.W.1.

**SITUATIONS VACANT.** Consulting engineers in Westminster require capable assistants for varied structural and civil engineering work. Five-days' week. Luncheon vouchers. Write or telephone: MAURICE NACHSHEN & PARTNERS, 58 Victoria Street, S.W.1, VIC. 0285.

### GENERAL MANAGER PRECAST CONCRETE PRODUCTS

Firm of precast concrete manufacturers, operating in central Scotland, having a progressive programme in hand, require a general manager, fully experienced in all types of precast concrete products. The appointment will relate particularly to the production side, but experience in all other branches will be necessary. An attractive salary and conditions, including superannuation scheme, will be offered to suitable applicant who should be in the 35-45 age group. Replies should give fullest particulars of experience and will be treated in strict confidence. Box 4643, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

### PARTNER.

Structural Consultant, N.W. London, in practice six years, is thinking in terms of rapid expansion and is interested in hearing from competent designer-draughtsman to take full charge of drawing office. Applicant should be prepared to enter partnership agreement and eventually to take over the growing practice. Write fully, in confidence, to BOX 4638, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

### SIMON-CARVES LTD.

have a vacancy in their Building & Civil Engineering Dept. for a

### FORMWORK DESIGNER/DETAILER

Applicants must have H.N.C. (Struct. or Mech.) or an equivalent standard of knowledge and wide experience of design and application of formwork structures for industrial and general civil engineering work. The post is permanent and pensionable and offers good prospects in an expanding department.

Starting salary up to £1,000, depending on experience and qualifications. Send brief relevant details to Staff and Training Division, SIMON-CARVES LTD., Cheadle Heath, Stockport, Cheshire, quoting Ref. ZR. 45.

### GEORGE WIMPEY & CO., LIMITED

invite applications from

### STEELWORK DESIGNER/ DETAILERS STEELWORK DETAILERS REINFORCED CONCRETE DESIGNER/DETAILERS REINFORCED CONCRETE DETAILERS

Rapid expansion of our Head Office organisation offers first-class opportunities for keen and experienced men in the field of Chemical and Refinery structures.

These appointments carry attractive salaries; personnel benefits include opportunity to join pension scheme, and full restaurant facilities.

Apply, giving full details of experience, to:

R. E. J. WORTH, M.I.C.E.,  
Planning Department,  
27 Hammermith Grove, London, W.6.

### "CONCRETE SERIES" BOOKS ON CONCRETE

(See also pages xxvii, lii, and lvi.)

For a complete catalogue giving prices in sterling and dollars, send a postcard to:  
**CONCRETE PUBLICATIONS, Ltd.**  
14 Dartmouth St., London, S.W.1



**SITUATIONS VACANT.** Experienced draughtsmen and draughtsmen in reinforced concrete required by consulting engineers in Golders Green. Progressive positions. Five-days' week, pension scheme. Box 4648, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

### DESIGN ENGINEERS AND DESIGNER-DETAILERS

Applications are invited for the following progressive and permanent appointments to our staff for a large and varied programme of reinforced and prestressed concrete work:

**DESIGN ENGINEERS.**—Chartered structural or civil engineers with several years' experience in design, and a good knowledge of structural theory. Quick, accurate and original designers, capable of working without supervision, preparing outline scheme drawings and estimating quantities for in situ and precast concrete structures.

**DESIGNER-DETAILERS.**—Capable of quick, accurate design and detailing from outline schemes.

Excellent working conditions in new offices near Manchester. Good salaries plus annual bonus, superannuation, three weeks' holiday. Written applications to:

MATTHEWS & MUMBY LIMITED,  
Oldham Street,  
Denton, Manchester.

### CIVIL ENGINEERING STAFF

#### SITE STAFF

The following are required for a variety of civil engineering contracts.

**Senior Agents** (Reference PE.8), having a minimum of ten years' experience with major contractors. Essential that applicants have had control of large competitive projects involving piling, excavation, and mass and reinforced concrete.

**Agents** (Reference PE.9) must have had up to five years' experience similar to the above on contracts of approximately £250,000 in value.

**Engineers** (Reference PE.10) must have had a minimum of two years' site experience on heavy civil engineering contracts and must have passed Parts A and B of Institution of Civil Engineers or have equivalent qualifications.

#### HEAD OFFICE STAFF

**Civil Engineer** (Reference PE.11) required to control staff who are engaged on construction-methods planning at the tender stage of contracts. Must have had considerable experience of site work, plant and labour utilisation and outputs, in the widest field of civil engineering. This is a new senior Head Office appointment, created by expansion, involving brief visits to sites.

All these posts are permanent and pensionable. Applicants should give full details of their age, experience, qualifications, present position and salary, and quote the reference number of the particular vacancy in which they are interested. Apply to SIMON-CARVES LIMITED, Contract Labour Department, Cheadle Heath, Stockport, Cheshire.

**SITUATION VACANT.** A well-known company of reinforced concrete engineers and contractors requires for an interesting vacancy in their London design office a well-qualified design engineer, with good experience both in the preparation of project schemes and working drawings. Salary up to £1600 per annum, with contributory pension scheme, etc. Box 4647, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

### ROBERT M. DOUGLAS (Contractors) LTD.

require

Designer-detailers immediately for work on multi-storey concrete structures. Apply, giving age, full details of experience, and salary required, to 395 George Road, Birmingham, 23.

### SITUATION WANTED.

**SITUATION WANTED.** Structural engineer, B.Sc., 30, with eight years' drawing office and site experience of in-situ and precast reinforced concrete, used to acting on own initiative and to carrying considerable responsibility, seeks senior position in London area where technical qualifications and experience can both be used to advantage. Good knowledge of languages. Box 4645, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

### PROFESSIONAL SERVICES.

**PROFESSIONAL SERVICES.** Structural engineer, experienced in the design and detailing of reinforced concrete and steel structures, will accept commissions from consulting engineers on a part-time basis. Box 4644, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

**PROFESSIONAL SERVICES.** Reinforced concrete engineer, with long experience, offers spare-time assistance to the profession. Designing and detailing. Box 4646, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

### FOR SALE, WANTED OR HIRE.

**FOR SALE.** Steel tubes and fittings, sections, strips, blanks, etc. List on request. E. STEPHENS & SON LTD., Bath Street, London, E.C.1. Telephone Clerkenwell 1731.

**FOR SALE.** Unused 500 tons three-mould concrete slab press, rotating table, self-contained oil hydraulic pumping unit, 400 tons two-station concrete slab press, by Fielding & Platt, with pumping unit. REED BROTHERS (ENGINEERING) LTD., Replant Works, Woolwich Industrial Estate, London, S.E.18. Tel. Woolwich 7611/6.

### WANTED.

COMPRESSION AND TRANSVERSE  
CONCRETE TESTING MACHINE  
REQUIRED. CAPACITY OF AT  
LEAST 150 TONS. PLEASE  
COMMUNICATE FULL DETAILS TO  
GEORGE W. BRUCE LIMITED,  
106 CROWN STREET, ABERDEEN

**FOR HIRE.** Lattice steel erection masts (light and heavy), 30 ft. to 150 ft. high, for immediate hire. BELLMAN, 21 Hobart House, Grosvenor Place, London, S.W.1.

### "CONCRETE SERIES"

### BOOKS ON CONCRETE

For a complete catalogue giving prices in sterling and dollars, send a postcard to:

CONCRETE PUBLICATIONS, Ltd.  
14 Dartmouth St., London, S.W.1



Practising  
at  
the Bar



Placing the case for Tentor Bar has its advantages; it has a clean record; it reinforces concrete extremely well, and is delivered promptly from six different places. Tentor Bars for concrete reinforcement set high standards in tensile and bond strength, save up to 15% of the cost of Plain Rounds, require no hooks, and can be supplied to meet contract requirements, cut or bent to specification, in sizes from  $\frac{3}{8}$ " to 1 $\frac{1}{2}$ "



Technical enquiries to:

**The Tentor Bar Company Ltd.**  
197 Knightsbridge, London,  
S.W.7. Telephone:  
KENington 6311. Telegrams:  
TENTORED, London, S.W.7

*Tentor Bars are supplied by the following companies and their branch offices:—*

**B.R.C. STEEL LTD.,**  
Siltmore Lane, Stafford. Stafford 444  
**G.K.N. REINFORCEMENTS LTD.,**  
197 Knightsbridge, London, S.W.7. KENington 6311  
**McCALL & CO. (SHEFFIELD) LTD.,**  
P.O. Box 21, Sheffield. Rotherham 2075  
**STEEL, FIECH & TOZER, LTD.,**  
Branch of The United Steel Companies Ltd.,  
The Idles, Sheffield. Sheffield 45011

**TENTOR BARS** Registered Trade Mark

**GLASGOW**

**NEWCASTLE**

**BELFAST**

**LIVERPOOL**

**LEEDS**

**MANCHESTER**

**DUBLIN**

**LEICESTER**

**STAFFORD**

**BIRMINGHAM**

**CARDIFF**

**BRISTOL**

**LONDON**

**BRC**

*Specialists in Reinforced Concrete Design  
and Suppliers of Reinforcement, with  
Design and Branch Offices strategically  
placed throughout the British Isles*

*The BRC service includes a Site Investigation Department*

**REINFORCED CONCRETE IS  
CONSTRUCTION AT ITS BEST**

There  
are vacancies  
for experienced  
engineers in several  
of our design offices.

*The British Reinforced Concrete Engineering Co. Ltd., Head Office & Works: Stafford*